

Historic, Archive Document

Do not assume content reflects current scientific knowledge, policies, or practices.



FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS



BEAUFORT COUNTY SOUTH CAROLINA

Prepared under sponsorship of
BEAUFORT COUNTY
BEAUFORT COUNTY DEVELOPMENT BOARD
and
BEAUFORT COUNTY SOIL AND WATER CONSERVATION DISTRICT
in cooperation with the
U. S. Department of Agriculture
Soil Conservation Service

U. S. DEPT. OF AGRICULTURE
NATIONAL AGRICULTURAL LIBRARY

April 1970

NOV 11 1970

NATIONAL

AGRICULTURAL



LIBRARY aTC977
.S6U5

301909

HOW TO

In order to easily
in this Drainage Fe

1. The approximate
2. Refer to figure
on this map.
3. This map will r
plan" in the ba
4. Turn to the map
map. When this
Number" and, al

ATA" SHEETS

ateral Canal contained
eps should be taken:

ould be known.

and locate the area

owing the drainage

5. Turn to this planning area number in the ENGINEERING AND DESIGN DATA
sheets and locate canal desired on this sheet.

e area desired on this
the "Planning Area
M-2, L-1, L-2, etc.

It must be kept in mind that the information given in the "ENGINEERING AND DESIGN DATA" sheets begins at the upper end of each watershed and proceeds, in order, to the outlet. Each time a lateral canal enters the main canal, the main canal is broken into a section at this point. Laterals are also broken into sections where additional laterals enter them. This was necessary for design purposes. Also, it was necessary to break mains and laterals into sections at state and county road crossings in order to design the proper size culverts and bridges at these points.

EXAMPLE: To find information for Huspah Creek where it is crossed by U.S. Route 17 and 21, approximately one mile west of the community of Gardens Corner, refer to Figure 3, "Index to Map Sheets." The index indicates that the point where Huspah Creek is crossed by the highway can be found on Sheet 1 of the maps at the back of the report.

Sheet 1 designates Huspah Creek as Main Canal No. 10, (M-10) of Planning Area Number 1. It also shows Lateral No. L-4, (L-4), to be the last lateral entering M-10 upstream from the highway crossing.

A general description of Planning Area Number 1 is found on page 11 of the report and the detailed Engineering and Design Data Table is on page 23.

Beginning at the upstream end of M-10 in the table for Area 1 on page 23, and proceeding downward toward its outlet end, it is found that M-10 is crossed by the highway 3500 feet downstream from the point where L-4 enters M-10. The various criteria for engineering and design may be obtained from the table at this line.

Foreword

The inter-relationship of man, water, and land has always been an important factor in the development and growth of any community. In Beaufort County, South Carolina, the absence of a well defined drainage pattern has hampered the proper development of this relationship.

Beaufort County, bounded on the south by the Atlantic Ocean, is made up almost entirely of lowlying islands. It contains an area of 637 square miles. The topography is generally flat.

The first inhabitants used the higher areas for farming operations leaving the low, wet lands in their natural state. As the need for more farm land arose, it was necessary to install some type of drainage system on individual farms. The drainage systems, usually constructed with slave labor, were small and inadequate and only partially met the drainage needs. No thought was given to the drainage of entire watersheds.

With the advent of modern construction machinery such as the bulldozer, dragline, and power shovel, it is economically feasible to construct the large canals needed for adequate drainage.

The Feasibility Study of Requirements for Main Drainage Canals in Beaufort County is the outgrowth of interest on the part of county authorities and the Beaufort County Soil and Water Conservation District supervisors, who, through their foresight, saw the need of such a plan in order to enhance the potential development of the county. This plan, as developed, is a direct result of such foresight. It is the first step towards solving the drainage needs of the county, which is recognized by all concerned as a problem of first priority. Agencies at all levels of government - local, county, state, and federal - as well as private enterprise and numerous individuals, cooperated in the development of the plan. The Beaufort County delegation appropriated funds for the local share cost of the plan, including the publication of this report. Technical assistance was furnished by the Soil Conservation Service, using funds furnished by the Lowcountry Resource Conservation and Development Project. This study is project measure No. 149 in the Lowcountry Project Plan and has received high priority by both the Commissioners and Beaufort County RC&D Group.

The plan will provide a firm basis for action by county officials in determining needed legislation and methods of financing the necessary drainage improvements as well as establishing priorities of work. The cooperation of other agencies, groups, and individuals in the use of the plan also will be encouraged.

CONTENTS

Text	PAGE	PAGE
INTRODUCTION AND SCOPE -----	1	DEFINITION OF TERMS ----- 15
FACTORS AFFECTING DRAINAGE -----	2	TECHNICAL REFERENCES ----- 18
Topography -----	2	AUTHORITY AND ACKNOWLEDGEMENT ----- 18
Tidal Ranges -----	2	EXPLANATION OF ENGINEERING DATA
Tide Gates and Pump Drainage ---	2	TABLES ----- 20
Rainfall -----	3	ENGINEERING AND DESIGN DATA
Soils -----	3	Area 1 - Yemassee-Sheldon-
Culverts -----	3	Lobeco ----- 22
Urbanization -----	3	Area 2 - Big Estate-Gardens
Existing Drainage System-----	6	Corner-Dale ----- 27
Maintenance -----	6	Area 3 - Port Royal Island ----- 29
DRAINAGE PRINCIPLES -----	6	Area 4 - Ladies Island-
Surface Drainage -----	6	St. Helena Island ----- 33
Sub-surface Drainage -----	6	Area 5 - Camp St. Mary-Okatie-
The Drainage System -----	7	Pinckney Colony-
The Collection System -----	7	Victoria Port ----- 43
The Disposal System -----	7	Area 6 - Hilton Head Island ----- 48
The Outlet -----	7	Area 7 - Prichardville-
DESIGN CRITERIA -----	8	Bluffton-
Drainage Coefficients -----	8	Daufuskie Island ----- 51
Velocity -----	8	MAPS SHOWING THE DRAINAGE PLAN
Channel Cross Section -----	8	Follows Page ----- 56
Values of Roughness		
Coefficient "n" -----	8	
Channel Depth and Width -----	10	
Side Slopes -----	10	
Design at Culverts -----	10	
Right-of-way Requirement		
Spoil Bank Management -----	11	
DESCRIPTION OF AREAS -----	11	
Area 1 - Yemassee-Sheldon-		
Lobeco -----	11	
Area 2 - Big Estate-Gardens		
Corner-Dale -----	12	
Area 3 - Port Royal Island -----	12	
Area 4 - Ladies Island-		
St. Helena Island -----	12	
Area 5 - Camp St. Mary-Okatie-		
Pinckney Colony-		
Victoria Port -----	13	
Area 6 - Hilton Head Island -----	13	
Area 7 - Prichardville-		
Bluffton-		
Daufuskie Island -----	13	
FACTORS CONSIDERED IN PREPARATION		
OF PLAN -----	14	
ENGINEERING CONSIDERATIONS -----	14	
Design -----	14	
Acquisitions of Rights-of-way --	15	
Maintenance of Channels -----	15	
Obstructions -----	15	

Figures

Figure No. 1 - Drainage	
Coefficient Curves -----	9
Figure No. 2 - Typical Main Ditch	
Cross Section Showing Basis for	
Determining Right-of-Way Width -	11
Figure No. 3 - Index to Map	
Sheets - Follows Page -----	56

Tables

Table No. 1 - Rainfall Data - U. S.	
Weather Bureau -----	4 & 5
Table No. 2 - Summary of Design	
Date by Areas -----	17

FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS BEAUFORT COUNTY, SOUTH CAROLINA

Introduction and Scope

The Feasibility Study of Requirements for Main Drainage Canals in Beaufort County is the logical first step toward solving the excess water problem. The purpose of the study is to point out the extent and severity of the drainage problem in the county and to furnish a guide to determine the physical feasibility and the estimated cost of the needed improvements. To accomplish this purpose, a system of main drainage canals has been developed for the major watersheds of the county and a discussion of some of the principal criteria used in design given.

The data in this report is based on reconnaissance surveys, information presently available, and on knowledge gained by long experience in planning and establishing drainage facilities

in the county. The data is adequate for the purpose of determining preliminary design and cost estimates, but is not adequate for the preparation of final construction plans, designs, and costs. The data herein presented, however, can be used by qualified engineers as guides in securing detailed information for these purposes. Included, also are technical references which can supply information for the final engineering investigations, plans, and designs.

The use of most of the land in Beaufort County is highly dependent on adequate drainage. The lack of drainage is the principal detriment to the development of the land resources of the county. It results in frequent and costly crop damage on agricultural land and to property damage and disruption of facilities, both public and private, in urban and industrial areas. The need to reduce flooding through improvement of drainage



PROJECT SPONSORS - These persons were directly responsible for development and publication of the 'Feasibility Study of Requirements for Main Drainage Canals in Beaufort County'. Left to right - top row: James M. Waddell, Jr., State Senator, District 13; James P. Harrelson, State Senator, District 13; Colden M. Battey, Jr., Chairman, County Council of Beaufort County; W. Brantley Harvey, Jr., Representative, Beaufort County. Bottom row: J. Wilton Graves, Representative, Beaufort County; H. E. McCracken, Vice-Chairman, Beaufort-Jasper Soil and Water Conservation District; A. T. Chalk, State Conservationist, Soil Conservation Service.
(Individual permission for the use of these photographs granted to Soil Conservation Service.)

canals is recognized as a problem of first priority.

Factors Affecting Drainage

The location of Beaufort County along the Atlantic Seaboard and its physical features result in complex drainage problems. The physical features that contribute to these problems are topography, high tidal ranges, rainfall, soils, and land use changes. All of these are inter-related. A brief discussion of how the physical features affect drainage follows.

Topography

Topography is a severely limiting factor affecting drainage. The land is generally level with slight undulations. Sharp breaks in topography occur along tidal streams and marshes. Elevations in the county range from mean sea level to 40 feet above mean sea level, with most of the drainage problems occurring between the 5-to 30-foot contour. The entire county outlets into tidal creeks and rivers which are subject to tidal fluctuations. The natural interior drains in most cases, outlet into these streams. The natural drains are broad, have flat grades, and are heavily vegetated. In their natural state, little or no channel exists, causing extreme ponding in depressed areas.

During periods of excessive rain and high tides many unimproved and paved roads are flooded to a degree that they are impassible.

Tidal Ranges

The tidal effects along creeks and rivers of the county are very complex, and highly variable, dependent on the velocity direction, and duration of winds and other weather events occurring seaward. Predicted or normal range of tides above mean low water, with no consideration of wind effects is 7.4 feet, with spring tides ranging to 8.7 feet. However, daily tide records maintained by the U. S. Weather Bureau, Charleston, South Carolina, show that there is considerable variation between the predicted and actual tide ranges due


to wind. Generally, tide heights have a departure of 1.0 to 1.5 feet below normal. Storm tides, which occur when sustained winds along the coast exceed 40 miles per hour, have a departure from normal of 2.0 to 3.0 feet above normal. A thorough knowledge of tidal action is essential in proper planning and design of drainage systems and supporting structures.

Tide Gates and Pump Drainage

No recommendations have been made in this study for the installation of tide gates or pump drainage due to varying conditions and the degree of protection desired. In many cases draining to mean low water is all that is necessary to furnish the desired protection.



Pump drainage may be necessary in some locations to achieve the desired protection from flood waters.



Residential Flooding - Causing property damage in many areas.

In other cases, tide gates may be necessary to eliminate the daily inflow of tide water. In urban, industrial, and other areas where the maximum protection is desirable, it may be necessary to install a combination of tide gates and pump drainage.

A more detailed study and survey would have to be made and a thorough knowledge of the planned use of the land in each individual watershed would have to be known in order to make a reasonable accurate recommendation for the installation of these structures.

Rainfall

U. S. Weather Bureau Records, Table No. 1, show monthly and yearly rainfall records for Beaufort, South Carolina. The average yearly rainfall of 46.78 inches would not cause a serious drainage problem if it were evenly distributed. The most serious drainage problem in areas along the tidal creeks is created by the high intensity, short duration rain storms occurring during periods of high tides and prevailing winds. The design of drainage systems and supporting structures is related to the amount of runoff that can be expected from storms of differing intensities and durations.


Soils

Soils have characteristics which decidedly influence the need for, and the degree of, drainage. Some of the more important characteristics are depth, infiltration, permeability, texture, structure, water-holding capacity, water-table depth, and slope. A knowledge of these characteristics, as well as of the engineering properties of soils, is essential in planning, designing, and constructing an adequate drainage system. Fine (clayey) textured soils have little or no sub-surface water movement and can be drained only by removal of surface water by means of shallow surface ditches. Sandy soils, having high water tables or fluctuating watertables, respond to subsurface drainage, but present problems in the design of open ditches. These problems include: (a) side slope sloughing, which limits depth of cuts; (b) limitation of the velocity of flow; and (c) sedimentation.

Culverts

Culverts for road and railroad drainage generally lack capacity to handle runoff from high intensity storms and are frequently installed with invert elevations too high. They are a serious bottleneck to the rapid disposal of runoff and cause local flooding. The problem is less severe on primary roads than on secondary roads. Culverts are predominantly inadequate on unpaved and farm roads.

Drainage structures in driveways paralleling streets and roads in established subdivisions are critical factors contributing to poor local drainage. Head losses alone, resulting from widespread use of under-designed culverts in residential areas, create local flooding conditions.



Highway culvert on right installed below original culvert, on left, to obtain adequate drainage for a newly constructed canal.

Urbanization

Urbanization of areas on Port Royal Island, Beaufort County, South Carolina, is having an adverse effect on drainage. Some of the drainage facilities now in use were established to handle the agricultural needs of the area. They are not adequate to handle runoff resulting from urbanization. Roof tops, paved roads, parking areas, compaction, raised water tables resulting from septic tanks and tile field installations, grading and elimination of some ditches during urban

TABLE NO. 1
RAINFALL DATA - U. S. WEATHER BUREAU
BEAUFORT COUNTY, SOUTH CAROLINA

TOTAL PRECIPITATION

Year	Jan.	Feb.	March	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Annual
1931	2.47	1.54	2.72	1.37	2.45	6.09	3.85	2.52	3.27	.50	.20	2.13	29.11
1932	1.55	1.43	3.35	.58	2.19	13.33	1.30	9.68	3.63	3.60	3.73	1.73	46.10
1933	4.40	6.88	1.13	2.01	2.03	3.76	5.77	8.86	6.61	3.30	1.06	-	-
1934	.79	1.66	1.12	1.06	5.20	1.04	1.50	2.65	2.82	1.78	1.37	1.28	22.27
1935	2.48	2.41	1.07	1.27	1.40	2.56	9.66	9.65	12.20	-	-	-	-
1936	3.33	3.59	3.11	2.50	.41	2.35	4.18	6.38	4.23	4.25	1.40	4.39	40.12
1937	3.76	4.40	2.44	5.73	1.52	9.67	6.73	5.40	4.56	2.42	4.23	.87	51.73
1938	.95	.74	.83	2.37	4.30	4.87	6.53	4.01	9.16	2.14	2.00	2.05	39.95
1939	1.38	7.40	2.19	3.61	3.63	7.18	5.43	11.92	.79	.30	1.10	2.40	47.33
1940	3.42	5.02	3.55	1.73	.91	4.30	5.81	14.51	1.86	T	1.46	3.67	46.24
1941	1.22	1.89	3.37	1.01	.44	11.34	3.23	3.27	1.01	.91	1.10	5.49	34.28
1942	3.97	3.14	4.58	.56	1.73	7.70	7.08	3.60	5.57	.02	1.30	3.24	42.49
1943	4.15	.75	7.39	2.31	2.68	5.41	7.05	7.23	.24	T	1.45	3.82	42.48
1944	4.10	5.30	9.75	7.28	2.13	1.74	3.95	9.30	4.13	5.00	1.56	.76	55.00
1945	2.03	3.32	1.49	4.04	2.03	3.84	7.40	5.10	18.00	1.69	1.01	4.94	54.89
1946	3.56	1.94	1.80	2.21	6.01	3.24	8.39	6.94	1.13	4.62	3.89	.81	44.54
1947	2.11	.31	6.66	3.60	3.35	6.39	2.60	5.77	11.32	3.06	5.39	7.91	58.47
1948	3.83	2.72	9.31	4.45	5.55	4.26	-	2.30	8.86	3.02	4.94	-	-
1949	.92	3.45	-	2.54	6.43	5.02	5.52	11.63	.48	-	.78	1.10	-
1950	1.19	.50	4.63	1.64	3.96	1.70	9.17	5.17	7.18	3.09	.65	4.19	43.07
1951	1.03	-	4.44	.90	1.26	3.11	7.32	2.48	5.54	3.44	2.05	2.89	-
1952	1.45	4.34	3.55	1.44	8.54	1.60	5.05	9.44	5.58	1.38	1.35	1.63	45.35
1953	2.19	5.66	8.39	1.09	2.23	4.50	4.35	3.92	10.93	T	1.34	5.71	50.31
1954	.70	1.44	1.06	1.35	6.67	2.32	5.57	1.51	4.73	2.70	2.35	3.05	33.45
1955	5.57	1.86	.37	3.51	2.77	5.71	2.26	4.73	5.12	.47	.85	.50	33.72
1956	1.94	2.63	2.25	3.08	.83	2.40	5.92	2.64	5.25	1.65	.44	1.24	30.27
1957	.47	2.12	4.09	2.66	12.01	5.31	11.89	2.24	4.49	2.11	4.74	1.89	54.02
1958	4.16	2.83	6.65	6.42	3.63	3.64	5.98	5.40	1.20	3.04	.55	1.61	45.11
1959	3.76	3.80	7.67	1.39	3.95	2.43	7.43	6.12	12.00	9.10	1.35	1.27	60.27
1960	5.61	4.59	3.27	2.51	4.19	1.58	15.25	2.81	5.72	1.17	.68	1.50	48.88
1961	2.35	3.85	6.27	5.07	3.75	5.60	6.70	13.83	2.92	T	.80	2.27	53.41
1962	3.83	1.26	6.28	3.63	3.84	13.64	3.03	4.80	4.26	2.02	2.24	1.73	50.56
1963	2.80	5.17	.70	3.05	3.34	16.26	3.60	5.81	4.49	.40	3.21	1.75	50.58
1964	6.78	6.66	3.54	2.80	4.89	5.84	22.69	9.83	7.16	6.09	1.59	3.68	81.55
1965	1.09	5.14	9.12	2.50	2.30	7.45	6.38	5.26	6.59	3.67	1.86	1.89	53.25
1966	6.12	3.87	5.10	1.67	10.32	5.45	9.59	7.96	1.32	1.01	.27	2.45	55.13
1967	7.40	3.33	1.03	2.20	6.83	3.71	12.41	6.67	2.85	0.30	1.89	3.14	51.76
1968	3.83	1.11	1.12	2.11	4.39	7.69	6.32	4.72	1.42	7.73	3.46	4.05	47.95
Average	2.97	3.19	3.93	2.61	3.79	5.37	6.67	6.21	5.23	2.69	1.88	2.66	46.78
Rain-fall													

In the above table information shown from January 1931 to December 1968 was taken from Beaufort, S. C. Station, U. S. Weather Bureau.

- No record available.

T Trace - not measurable.

TABLE NO. 1 (continued)
PRECIPITATION EXTREMES

	Maximum Monthly	Year	Minimum Monthly	Year
January	7.40	1967	0.47	1957
February	7.40	1939	0.31	1947
March	9.75	1944	0.37	1955
April	7.28	1944	0.58	1932
May	12.01	1957	0.41	1936
June	16.26	1963	1.04	1934
July	22.69	1964	1.30	1932
August	14.51	1940	1.51	1954
September	18.00	1945	0.24	1943
October	9.10	1959	T*	1940
October	-	-	T	1943
October	-	-	T	1953
October	-	-	T	1961
November	5.39	1947	0.20	1931
December	7.91	1947	0.50	1955

* T means Trace - not enough to measure.

RAINFALL IN INCHES FOR SELECTED DURATIONS*

	30 Min.	1 Hour	2 Hours	3 Hours	6 Hours	12 Hours	24 Hours
1 year	1.4	1.8	2.2	2.3	2.7	3.2	3.7
2 years	1.6	2.2	2.5	2.7	3.2	3.8	4.5
5 years	2.0	2.6	3.1	3.5	4.2	5.0	5.8
10 years	2.3	2.9	3.6	4.0	4.8	5.8	6.8
25 years	2.6	3.3	4.1	4.6	5.6	6.8	7.8
50 years	2.9	3.7	4.6	5.2	6.3	7.5	8.6
100 years	3.1	4.0	5.2	5.7	7.0	8.3	9.9

* U. S. Weather Bureau Technical Paper No. 40 - "Rainfall Frequency Atlas of the United States."

development, have created conditions approaching 100 percent runoff. As urbanization continues, the present drainage facilities will become increasingly inadequate to handle runoff.

There is a need for regulations to insure that adequate drainage canals and drainage structures are installed as these areas develop.



Bridge Washout - Caused by period of intensive rainfall and lack of an adequate channel.

Existing Drainage System

With the exception of some recently excavated canals, drainage systems in rural and urban areas are generally inadequate in depth and capacity and have very flat grades. An important additional factor contributing to this problem is the lack of legal authority to secure adequate rights-of-way for proper ditch design, spoil management, and access for maintenance. Rights-of-way, in the past, were usually limited to the width which the landowner was willing to donate, which, in most cases, was less than 30 feet.

Existing flat grades are the results of discharging canals - (1) into tidal marshes at mean sea level elevation rather than at mean low water elevation, or (2) discharging into swamps which are not adequate outlets in their present state since they generally pond water for long periods of time following heavy rainfall.

Existing canals are usually located in natural water courses. However, in many instances, alignment is poor since attempts were made to accommodate the canals to existing property lines or other physical features inconsistent with good channel flow conditions.

Maintenance

Lack of maintenance in the past resulted in dense growth of trees on high spoil banks adjacent to channels; some enlargements were completed in the 1930's, leaving vertical side slopes. Dense tree growth, high spoil banks and absence of legal easements for access has eliminated machine maintenance. Continuous spoil banks existing on both sides of channel has eliminated side drainage.

Drainage Principles

This plan designates the location and needed capacities of main drainage canals. This is, however, only the first step in the establishment of a complete drainage system. Drainage systems are divided into two broad categories -- surface drainage, and subsurface drainage.

Surface Drainage

Surface drainage removes excess water, by gravity, from the land surface to an outlet. The important functions of the surface drainage system is:

- (1) To insure movement of surface water to the outlet without ponding.
- (2) Collect water and convey it to natural outlets in constructed channels.

Surface drainage is necessary for successful crop growth on soils having slow permeability rates.

Sub-surface Drainage

Sub-surface drainage lowers the water table beneath the surface of the soil by facilities which create a difference in hydraulic head. The resulting hydraulic head causes water to move through the soil

to an outlet. Sub-surface drainage may be accomplished by open ditch drains and or tile drains. Open ditch drains have an added advantage because they can also collect and remove surface water. Tile drains require very little maintenance, and with certain precautions, can remove surface water by simulating small storm sewer systems.

The purpose of sub-surface drainage is to lower the water table to a point where it will not interfere with plant growth or the use of the land for residential or other purposes. The minimum depth below the surface at which water tables should be maintained depends on the use of the land. Water tables, fluctuating upward to or near the surface, may not be as great a problem in agricultural areas as they would be in populated areas.

The Drainage System

The components of a drainage system are as follows:

The Collection System - is that part of the drainage system which first picks up water from the land. It may consist of:

- (1) Shallow trapezoidal ditches, having flat side slopes.
- (2) V or W-type ditches.
- (3) Bedding.
- (4) Grading the land surface in urban areas.

This part of the drainage system cannot be neglected if the system is to perform adequately.

The Disposal System - receives water from the collection system and conveys it in a channel to an outlet.

The Outlet - is the end point of any segment of a drainage system beyond which the ditch, storm sewer, or the system no longer guides or controls the water it discharges. Generally, this report concerns itself with "The Disposal System."

Drainage Requirements

The drainage system should be designed so that flooding will not occur in critical parts of the watershed for a period of time sufficient to cause damage or disrupt

utilities and services. For urban areas, design should provide for the removal of runoff from the design storm with a minimum of flooding. In agricultural areas, the degree of protection required by crops varies considerably, depending on their tolerance to the amount and duration of excess water. Truck crops are the most susceptible to damage from excess surface water, with damage occurring to some when flooded for the relatively short period of 24 hours or less. General crops such as corn and grain are less susceptible, with pasture being the least subject to water damage. Woodland areas are the least subject to damage from flooding for prolonged periods.

Poorly drained soils adversely affect the use of the land for most purposes. On agricultural land, high water tables restrict root penetration; soil temperature is lowered, air circulation is severely limited, dependent on the degree of soil saturation. Wet spots in the field delay farm operations and shorten the growing season.



Flooding caused by heavy rainfall and lack of adequate drainage channel.



Water Ponding In Corn Field - Caused by lack of proper drainage.

Design Criteria

The design of drainage systems and supporting structures is based on hydrology and hydraulics and this report will limit itself to the application of these sciences as they apply to the solution of such problems. References for more detailed information on design of open channels, closed conduits, culverts, and other engineering structures ultimately involved in establishing a drainage system are listed on pages

Drainage Coefficients

The drainage coefficient is the rate of removal of runoff to provide a specific degree of drainage protection to an area. Land use, soils, topography and rainfall intensifies and duration determine the selection of drainage coefficients. A series of five curves have been developed from which required drainage capacities of open ditches were computed, dependent on the land use. (See Figure No. 1.)

The highest curve is for urban use followed in descending order for crops, improved pasture, and woodland.

The use of these curves provides for the removal, in 24 hours time, of the following amounts of runoff:

Urban curve	- 4.39 inches
Truck crops	- 3.33 inches
General crops	- 1.67 inches
Improved pasture	- 0.93 inches
Woodland	- 0.37 inches

The curve for urban areas reflects a peak runoff for a 10-year frequency rain - 100-year frequency rains may be designed for if needed.

Velocity

Soil characteristics, the shape of the channel, and available means for stabilization of the soil after construction, determine the maximum safe velocity. The optimum velocity for channels, based on soil conditions in Beaufort County, is approximately two feet per second. The soils are predominantly fine sands. Sedimentation occurs when velocities are less than 1.5 feet per second which is frequently caused by vegetative growth.

Erosion will occur in most soils at velocities in excess of 3.0 feet per second. Design of channels in the fine, water-bearing sands must consider the need for checking erosion and bank sloughing that will occur immediately following construction when water tables are high.

Velocities should be designed after a thorough investigation of soil conditions to the depth of proposed channels.

Channel Cross Section

Values of Roughness Coefficient "n".

All channel cross sections were computed by use of Manning's formula for determining velocities.

This is:
$$V = \frac{1.486}{n} \times r^{2/3} \times s^{1/2}$$

where: n = Roughness coefficient
r = Hydraulic radius
s = Slope in feet per foot along ditch

The proper design of a ditch cross section requires the selection of the proper value of "n". Side slopes of the ditch, as well as depth and allowable velocities, are fixed primarily by soil conditions and proposed maintenance methods.

The following tabulations were used for selection of values of "n" for Manning's formula in the design of main canals with good alignment:

Hydraulic Radius*	"n"
Less than 2.5	.045
2.5 to 4.0	.040
4.0 to 5.0	.035
over 5.0	.030

*The hydraulic radius is obtained by dividing the proposed area of channel cross section by its wetted perimeter.

In newly dug channels the roughness coefficient is lower and velocities higher. A realistic roughness coefficient was selected anticipating flow retardance features, such as vegetative growth and sediment several years after construction.




Figure No. 1 - Drainage Coefficient Curves

Channel Depth and Width

Depth of channel is an important design consideration. The channel must be deep enough to tap and provide for the escape of ground water, and to provide for the safe entrance of the longer lateral ditches and tile drains. Other considerations favoring a deeper channel with a resulting narrower bottom width are: less right-of-way is required, vegetative growth on the wetted perimeter is reduced, and conditions are less favorable for the formation of sandbars. A channel roughly as deep as its bottom width, within economic limits will remain effective for a longer period because it has most favorable hydraulic characteristics.

A minimum bottom width of 3.0 feet was designed for main channels, which conforms to a bucket width of small dragline excavating equipment; bottom widths were selected as narrow as design and construction criteria would permit so as to obtain higher velocities which, in many instances, due to low gradients were not high enough to prevent formation of sediment islands and growth of vegetation in channel bottoms.



Lateral Canal - This canal shows importance of good construction, alignment, spoil management, and erosion control on side slopes.

Side Slopes

Maintenance methods, soil characteristics, and a need for adequate but economic minimum rights-of-way determined the side slopes of channels. Side slopes of 1 to 1 for main channels were used to satisfy these conditions.

In fine sands having high water tables, sloughing of side slopes may be expected immediately after excavation. Sloughing will continue until the water table becomes established at the lower level. The problem can be controlled somewhat in wide channels by requiring initial construction of a pilot channel to lower the water table, followed by final construction when the channel has been stabilized; or, by requiring a maintenance operation to restore design cross section soon after the channel has been stabilized.



Tile Drainage - This is a tile machine in the process of installing farm drain tile lines. The demand is greater each year for these underground drainage systems.

Design at Culverts

Culverts obstruct the flow of water in ditches and cause a loss in head. This was considered in designing main channels. The hydraulic gradient, in most cases, was set low enough to keep the profile of the water surface at the culvert during design flow well within the channel cross section in all critical areas.

Talbot's formula was used in determining culvert sizes. Talbot's formula is as follows:

$$\text{where: } A = C \sqrt[4]{\frac{3}{M}}$$

where: A = Necessary waterway in sq. ft.
M = Area drained in acres
C = Coefficient (.2 used)

Where culvert sizes exceed 60 inches in diameter, it was usually found more economical to use 15-foot bridges.




Figure No. 2 - Typical Main Ditch Cross-Section Showing Basis For Determining Right-Of-Way Width

Right-of-way Requirement- Spoil Bank Management

Factors governing width of rights-of-way can best be understood by consulting Figure No. 2. The principal requirements for spoil bank management includes a right-of-way wide enough for placement of spoil and shaping of spoil into roadway to provide a way for travel by maintenance equipment. No berm widths are needed where the spoil is to be spread and shaped to establish a roadway on top of it.



Right-of-Way Clearing for main drainage canal.

Description of Areas

The county was divided into 7 areas to delineate the drainage needs peculiar to these areas and to facilitate planning. A brief description of drainage problems associated with each area follows:

Area 1 - Yemassee - Sheldon - Lobeco

This area is bounded on the north by Hampton County line and the Combahee River; on the west by the Pocatoligo River and the Jasper County line; on the south by Whale Branch and the eastern boundary begins at Sugar Hill Creek on the north and extends in a southerly direction to Whale Branch.

A large portion of this areas is owned by large land owners. Farming operations are cattle, row crops, woodland, and wildlife. The remaining acreage is devoted to intensified truck crops. Principal truck crops are cucumbers, tomatoes, snapbeans, and leafy vegetables.

During periods of heavy rainfall a very large portion of this area is subject to excessive flooding due to inadequate outlets

and water-control structures.

A wide range of soils and soil conditions occur in this area. They range from well drained loamy sands to poorly drained clays. The majority of the soils are productive sandy loams that require moderate to intensive drainage for most land use. Most of the soils have a high site index for timber production, but removal of excess water in low-lying areas is necessary for the establishment and management of the desired species of trees.

Area 2 - Big Estate - Gardens Corner - Dale

Area 2 is bounded on the north and east by the Combahee River, on the south by Coosaw River, and on the west by Sugar Hill Creek extending in a southerly direction for approximately 10 miles to Whale Branch.

Approximately 25% of the area is devoted to truck crops such as tomatoes, cucumbers, snapbeans, squash, and leafy vegetables. Also, general row crops comprise about 25% of the area. The remainder of the area is being used for timber production, pasture, and wildlife. Of the last three mentioned, woodland is the most important and largest of the three. The soils have a high site index for timber growth, but removal of excess water is necessary for the management and the establishment of desired species.

There is a wide range of soils and soil conditions within the area. They range from well drained loamy sands to poorly drained clays. The larger portion of the soils are productive sandy loams that require moderate to intensive drainage for most land use.

Area 3 - Port Royal Island

Area 3 is bounded on the north by Whale Branch and Coosaw River; on the east by Beaufort River; and on the south and west by Port Royal Sound.

This area includes the majority of the population of the county. It includes the city of Beaufort, Port Royal, U. S. Naval Hospital, U. S. Marine Corps Air Station, and Capehart Housing Project. A rapid change from agricultural to urban

and industrial use is taking place in a large portion of Port Royal Island. It is a trend that is expected to continue. Most of the existing drainage on Port Royal Island was installed to take care of the agricultural needs of the island, and not for urban or industrial development. As urbanization and industrialization continues in this area, the need for drainage improvements will become more and more critical. These improvements should anticipate expected developments which can now be established without too much difficulty and at a more reasonable cost.

The agronomic work in this area is devoted primarily to intensive truck crops such as tomatoes, cucumbers, snapbeans, and squash.

Soils in this area are dominately sands and loamy sands. Areas of finer textured soils occur in the vicinity of Seabrook, as well as other small areas throughout Area 3. These soils range from well drained to very poorly drained, with a large majority requiring some degree of drainage for most land users. Wind erosion on the larger well drained sandy soils is a moderate problem under certain conditions.

Area 4 - Ladies Island - St. Helena Island

This area is located in the southeastern portion of Beaufort County. Area 4 is bounded on the north and east by Coosaw River and St. Helena Sound; on the south by Harbor River and Station Creek; on the west by Port Royal Sound and Beaufort River. The small privately-owned islands, south and east of Station Creek and Harbor River, were excluded from this study.

This area contains a number of large and small truck farms. Good drainage is essential to the production of truck crops. Most truck farms are located along tidal creeks where better drained soils, well suited to truck crops, are found, and where outlets into tidal creeks are readily available. Farms located further inland require main drains to tidewater for disposal of runoff. The topography is flat with some large depressions which pond water.

A great portion of the high land is in a rotation of truck crops and general crops.

Truck crops grown are tomatoes, cucumbers, squash, snapbeans, and some leafy vegetables. Due to the long growing season, ease of tillage and other favorable factors, this area is well suited to truck crops. Other crops grown are corn, soybeans, and small grain. Some of the area is being used for pasture land, woodland, wildlife, and recreation.

Soils in this area are dominately sands and loamy sands, with small areas of soils underlain by sandy clay loams. These soils range from excessively drained to very poorly drained. The natural drainageways generally parallel the coast. Well planned drainage programs are needed to enhance both the agricultural and residential potential of the area.

Area 5 - Camp St. Mary - Okatie - Pinckney Colony - Victoria Port

Area 5 is bounded on the north by Jasper County line and Broad River; on the east by Broad River, Port Royal Sound, and Mackays Creek; on the south by a line from Mackays Creek westward to Great Swamp; and on the west by Jasper County line.

The greater part of this area is devoted to timber production, with several large tracts of land owned by a Paper and Pulp Company. Most of the agronomic practices are devoted to livestock production. Crops grown to support livestock production are hay and pasture. Also, some general row crops are grown.

Wildlife is also an important management practice. With an abundance of turkey, deer, and squirrel, some income is derived by the landowners leasing their lands to hunting clubs.

Soils range from well drained droughty sands to poorly drained fine sandy loams with an appreciable acreage of organic hardpan. The soils along the northwest boundary of this area are underlain with sandy clay loams. In general, the Sea Islands are sandy and surrounded by large areas of tidal marsh.

Area 6 - Hilton Head Island

Hilton Head Island is bounded on the north by Port Royal Sound; on the east and south

by the Atlantic Ocean; and on the west by Calibogue Sound and Mackays Creek.

This area is rapidly being developed into an exclusive year-round resort and urban area. It is a trend that is expected to continue. There is an opportunity on Hilton Head Island to install adequate drainage facilities and related engineering structures before the island becomes totally urbanized. This work can now be accomplished at less cost and with a minimum of difficulty in acquiring rights-of-way. Encroachment of developments on areas exposed to storm tides makes special protective measures such as dikes, tide gates, and pumps necessary. Much of the drainage needed is already being installed by large real estate developers in the area.

The limited amount of agronomic work is truck crops such as tomatoes, cucumbers, and butterbeans.

This area is composed of Sea Islands, with Hilton Head Island dominating the area. Soils are dominantly sands, ranging from excessively to very poorly drained sands. The poorly drained sands are often underlain with organic hardpans. In almost every instance the drainage pattern parallels the ocean.

Area 7 - Prichardville - Bluffton - Daufuskie Island

This area is bounded on the north by a line running from Great Swamp easterly to Mackay Creek; on the east by Mackay Creek and Calibogue Sound; on the south by the Atlantic Ocean and Intra Coastal Waterway; and on the west by New River.

There are several large tracts of land in this area owned by paper and pulp companies which are managed for timber production and wildlife. Livestock production is the main agronomic practice in this area. Crops grown to support livestock production are hay and pasture. Also, some general row crops are grown.

Wildlife is also an important management practice within this area. With an abundance of turkey, deer, and squirrel, some income is derived by the landowners leasing their lands to hunting clubs.

The major portion of the soils are sands, ranging from excessively drained to very

poorly drained. A large portion of the poorly drained sands have an organic hardpan. A small area along New River is underlain with sandy clay loams or clays. A significant portion of the area is tidal marshland.

Factors Considered in Preparation of Plan

The Drainage Feasibility Study was prepared by engineers of the Soil Conservation Service with the assistance of the Beaufort County Council and County Supervisor's office. On-site investigations were made of the outlets for each main canal, and the factors affecting drainage within the watershed, such as tidal ranges, river stages, flooding and the time of year in which flooding occurs, were studied.

Present land use and anticipate future land use was considered in preparing the design of drainage canals. Engineering information available through the Beaufort County Work Unit office of the Soil Conservation Service was also used, particularly that pertaining to drainage investigations.

U. S. Geological Survey Topographic Maps were used to determine the general topography within each watershed and to assist in delineation of watersheds. A limited amount of instrument surveying was made to secure detailed information in critical areas.

Aerial photographs, scale 1"=1320', flown in 1965, were used in recording field data and for the preparation of the drainage plan.

Agencies and commercial concerns, having knowledge of specific drainage problems were consulted in making the final decisions in certain areas. Also, maps, surveys, and plans available from these agencies were used.

In most instances, mains were located along natural drains with modifications in alignment to improve the flow and the collection of water. All needed laterals within the watersheds were not located since the purpose of the study is to locate and design only the main canals which will furnish the means of disposal of runoff from all parts of the watershed. All mains are terminated in tidal creeks or natural outlets at a point where they have adequate capacity and depth.

No attempt was made to locate underground utilities such as cables, gas pipelines, water mains, and conduits as a part of this study. However, due consideration must be given to the location of these underground utilities during the preparation of the final plans.

In general, the drainage plan was limited to areas considered as "high lands" - that is, five feet or more above mean low water.

Watersheds draining into the county from adjoining counties were determined for the purpose of designing main canals. The mains, however, are shown beginning at the county line. Due attention was given to possible land use changes which would affect runoff within the portion of these watersheds in adjacent counties.

Engineering Considerations

Engineering considerations for planning, design, construction, maintenance, and other matters pertinent to the Main Drainage Canals Feasibility Study are listed below:

Design

1. The plan presented herewith is a Feasibility Study to estimate the cost and the extent of needed main drainage facilities and the physical practicability of drainage in the county. Detailed engineering surveys and designs will be required before any part of the proposed plan is constructed. All improvements should be made continuous, beginning at the lower or outlet end of the watershed.
2. Plans and designs contained in this report do not include a complete study of underground storm sewers found in Areas 1, 3, 6, and 7, due to the fact that these are not considered as mains. Also, there is a lack of information on original surveys and designs showing size, depth, and location. Detailed studies will be needed to determine the present condition of these storm sewers and their additional needs.
3. Culverts at railroad and road crossings were designed to satisfy the minimum requirements based on expected flow. Increases in size of these structures may be desirable to provide an added safety factor for passing runoff in excess of designed flow; especially where presently unforeseen improvements are made in the vicinity.

4. The South Carolina Wildlife Resources Department should be consulted when fish and wildlife may be affected by the construction of main drainage canals.

Acquisition of Rights-of-way

The means for and the acquisition of adequate rights-of-way for the installation of main canals is absolutely essential. The right-of-way must be adequate to take care of width requirements for channel section, berm, spoil management and access. (See Figure No. 2)

Maintenance of Channels

A well organized and adequately financed maintenance program is essential to maintain design capacity in all canals. Provision for annual maintenance or periodic reconstruction to maintain the effectiveness of the channel must be considered prior to construction. The failure of many drainage enterprises to function as designed can be directly attributed to an inadequate maintenance program. Maintenance of designed depth of channels is one of the most important items in a maintenance program. The cost of maintenance may be reduced considerably if provision is made in channel designs for easy access, stabilization of side slopes, and other silt-contributing areas such as road fills and road drainage immediately following construction.

Obstructions

Construction of fences, walks, and other structures, that may retard channel flow, should not be permitted except as approved by the responsible agency of the County Government. Other structures such as culverts, bridge piers, trestles, etc., should be designed so as to cause minimum interference with the channel flow. Dumping trash, garbage, and other debris in channels should be prohibited.

Definition of Terms

Brief descriptions of terms used in this report are listed below in alphabetical order:

c.f.s. - Abbreviation for cubic feet per second; an unit of water-flow sometimes called "second feet."

Infiltration - The entrance of water into surface of soil.

Internal Drainage - The movement of water through the soil profile. The rate is affected by the texture of the surface soil and of the subsoil and by the height of the water table. A wet, deep sand may have slow internal drainage when the water table is high, and rapid internal drainage when the water table is low. A plastic, sandy clay soil may have slow internal drainage regardless of water table height.

Lateral Ditch - A major ditch in a drainage system which serves as a link between the main ditch and the collection system in a segment of the watershed.

Main Canal (Ditch or Channel) - The principal channel which conducts the drainage water from the watershed to the outlet.

Permeability Rate - The rate of movement of water through the soil.

Profile, Soil - A vertical section of the soil through all its horizons and extending into the parent material.

Reach - A length of channel selected for use in hydraulic computations.

Relief - The elevations, or inequalities, of a land surface considered collectively.

Runoff, Surface - Total rainfall minus losses from interception, infiltration, evaporation, and surface storage; that which moves across the ground to a stream or depression.

Runoff, Subsurface - Water that infiltrates the soil and reappears as seepage or spring flow.

Soil Drainage - (1) The rapidity and extent of the removal of water from the soil by runoff and flow through the soil to underground spaces, (2) As a condition of the soil, the frequency and duration of periods when the soil is free of saturation - for example: in well drained soils, the water is removed readily but not rapidly; in poorly drained, the root zone is waterlogged for long periods and the roots of ordinary crop plants cannot get enough oxygen; and in excessively drained soils, the water is removed so completely that most crop plants are damaged by lack of water.

Definition of Terms (continued)

Soil Structure - The arrangement of the individual grains and aggregates that make up the soil mass; may refer to the natural arrangements of the soil when in place and undisturbed, or to the soil at any degree of disturbance.

Subsoil - In soils with weak profile development, the subsoil can be defined as the soil below the plowed soil (or its equivalent of surface soil) in which roots normally grow.

Surface Soil - The soil ordinarily moved in tillage or the equivalent in uncultivated soil about six to ten inches in thickness.

Terrace (Geological) - An old alluvial plain ordinarily flat or undulating, bordering a river, lake, or the sea. Stream terraces are frequently called second bottoms, as contrasted to flood plains, and are seldom subject to overflow. Marine terraces were deposited by the sea and are generally wide.

Texture, Soil - The relative proportions of sand, silt, and clay particles in a mass of soil. The basic textural classes, in order of increasing proportions of fine particles, are as follows: sand, loamy sand, sandy loam, silt loam, silt, sandy clay loam, clay loam, silty clay loam, sandy clay, silty clay, and clay. The sand, loamy sand, and sandy loam classes may be further divided by specifying "coarse", "fine", or "very fine". A coarse-textured soil is one high in sand content; a fine-textured soil is one high in clay content.

Tide Data

Mean Range - Difference between mean high water and mean low water.

Spring Range - The average range which occurs semi-monthly as a result of the moon's being full or new.

Mean Tide Level (Half tide level) - is a plane midway between mean low water and mean high water.

High Water - The maximum height reached by each rising tide.

Water-holding Capacity - The ability of a soil to hold water. The capacity (or ability) of soil to hold water against gravity.

Watershed - An area of land from which all water that falls within the area, converges toward and discharges past a designated point.

TABLE NO. 2
SUMMARY OF ENGINEERING AND DESIGN DATA BY AREAS

Area Number	Length of Canals Feet	Excavation Cubic Yards	Right-of-way Clearing Acres	Estimated Total Cost Dollars / <u>1</u>
1	310,900	567,130	152.4	326,963.80
2	171,400	332,412	132.2	190,623.00
3	208,750	392,971	162.8	240,357.60
4	396,700	602,505	299.0	313,906.30
5	298,900	481,371	220.9	236,853.30
6	165,800	291,383	133.2	151,742.10
7	440,400	714,738	344.4	344,084.40
<hr/>				
Sub-				
Totals	1,992,850	3,382,510	1,444.9	1,804,530.50
Plus 15% added for contingencies-				270,679.57
<hr/>				
County				
Totals	1,992,850	3,382,510	1,444.9	2,075,210.07

1/ Based on 1969 prices.

Technical References

C. E. Ramser - FLOW OF WATER IN DRAINAGE CHANNELS - U. S. Department of Agriculture - Technical Bulletin No. 129 - U. S. Government Printing Office - Washington, D. C.

H. W. King - HANDBOOK OF HYDRAULICS - McGraw-Hill Book Company, Inc., New York, N. Y.

War Department, Corps of Engineers - HYDRAULIC TABLES - U. S. Government Printing Office, Washington, D. C.

U. S. Department of Agriculture, Soil Conservation Service - NATIONAL ENGINEERING HANDBOOK - DRAINAGE - Section 16, Chapters 1, 2, 3, 4, 5, and 6.

U. S. Department of Agriculture, Soil Conservation Service - NATIONAL ENGINEERING HANDBOOK - HYDRAULICS - Section 5.

U. S. Department of Agriculture, Soil Conservation Service - FIELD DRAINAGE GUIDE FOR SOUTH CAROLINA.

U. S. Department of Commerce, Weather Bureau - TECHNICAL PAPER NO. 40 - RAINFALL, FREQUENCY ATLAS OF THE UNITED STATES - U. S. Government Printing Office - Washington, D. C.

U. S. Department of Agriculture, Soil Conservation Service - NATIONAL ENGINEERING HANDBOOK - HYDROLOGY - Section 4.

FEASIBILITY STUDY FOR MAIN DRAINAGE CANALS in Colleton County.

Authority and Acknowledgement

Authorization for preparation of the Feasibility Study of Requirements for Main Drainage Canals for Beaufort County is the result of a cooperative agreement entered into on March 10, 1967, by:

Beaufort County - J. M. Waddell, Jr., State Senator
J. Wilton Graves, Member of House of Representatives
W. Brantley Harvey, Member of House of Representatives

County Council of Beaufort County -

Colden R. Battey, Jr., Chairman
Arthur B. Horne, Jr., Vice-Chairman
Leroy E. Brown
John P. Dennis
David Jones
Omar D. Horton
Jerry H. Reeves, III
Grady D. Thames
Booker T. Washington
A. R. McAfee, Administrative Officer

Beaufort Soil and Water Conservation District

Soil Conservation Service - A. T. Chalk, State Conservationist

Administrative supervision for Soil Conservation Service - W. Lee Colburn, Area Conservationist.

Authority and Acknowledgement (continued)

Direct responsibility for preparation of plans, designs, and final report was as follows:

C. C. Allen, Civil Engineer, Soil Conservation Service
A. C. Utsey, Jr., Engineering Technician, Soil Conservation Service
C. C. Haigh, Beaufort County Supervisor

Special technical assistance during all phases of the preparation of this report was given by:

S. Taylor Currin, State Conservation Engineer, Soil Conservation Service
W. M. Stuck, Soil Scientist, Soil Conservation Service
R. E. McLin, District Conservationist, Soil Conservation Service

Other who furnished data, information, or services used in the preparation of this report are as follows:

U. S. Weather Bureau

South Carolina Highway Department

U. S. Marine Corps

Union Camp and Paper Company

Cartography and Printing - Fort Worth Cartographic Unit, Soil Conservation Service

Explanation of Engineering Data Tables

The following Engineering Data Tables contain information, by areas, for each main canal and lateral, by watersheds.

An explanation of each column in the Engineering Data sheets is as follows:

Column 1 CANAL NUMBER
Numbering of main canals begin with M-1 and laterals with L-1, in each area.

Column 2 LENGTH IN FEET
The stationing of all mains and laterals begins at the upper end (headwaters) and continues toward the outlet. The mains and laterals are shown in reaches or sections in the data tables for design purposes. Each reach or section reflects a change in water concentration resulting from the entrance of lateral drainage.

Column 3 WATERSHED IN ACRES
See definition of terms.

Column 4 DISCHARGE-CUBIC FEET PER SECOND
From appropriate drainage coefficient curves dependent on the land use.

Column 5 TOP WIDTH IN FEET
Self explanatory

Column 6 BOTTOM WIDTH IN FEET
Self explanatory

Column 7 AVERAGE DEPTH IN FEET
Self explanatory

Column 8 EXCAVATION IN CUBIC YARDS
Self explanatory

Column 9 RIGHT-OF-WAY CLEARING IN ACRES
Self explanatory

Column 10 REQUIRED RIGHT-OF-WAY WIDTH IN FEET
Based on minimum requirements for channel cross section, spoil management, berm width, and access road for maintenance equipment.

Column 11 CULVERTS, LOWERING-LENGTH AND SIZE
Refers to the existing in-place culverts which are to be re-used.

Column 12 CULVERTS, BRIDGES, AND TRETTLES NEW - LENGTH AND SIZE
Refers to additional culverts, bridges, and trestles required to handle design discharge. Design of culverts is based on round concrete pipe.

R. C. Br. - Reinforced concrete bridge
C. T. Br. - Creosoted timber bridge
U. T. Br. - Untreated timber bridge
C. T. Tres.-Creosoted timber trestle

Column 13 TOTAL ESTIMATED COST IN DOLLARS
Total costs shown include only the estimated construction costs and do not include engineering costs, and the cost of acquiring required right-of-way. When preparing the final cost estimates these engineering costs and right-of-way costs should be included in the total cost of the project. Total estimated costs, as shown, are based on the following unit prices prevailing in Beaufort County in 1969.

EXCAVATION

Rural Area-High Ground - \$0.30 per cu.yd.
Urban - \$0.60 per cu.yd.
Marsh - \$0.60 per cu.yd.

RIGHT-OF-WAY CLEARING AND GRUBBING

Rural area - \$300.00 per acre
Urban area - \$500.00 per acre

LOWERING EXISTING CULVERTS

Labor and equipment costs only.

NEW CULVERT AND CONDUIT COSTS

Based on present cost of circular concrete pipe.

BRIDGES

Three types of bridges were used for design purposes:

1. Precast reinforced concrete bridges were used under main highways and secondary roads.

Explanation of Engineering Data Tables (continued)

2. Pressure-treated creosoted timber bridges were used under county roads.
3. Untreated timber bridges were used on farm and private roads.

PREVAILING COST OF BRIDGES

Reinforced concrete bridges	- \$100.00
per linear foot	
Creosoted timber bridges	- \$ 50.00
per linear foot	
Untreated timber bridges	- \$ 33.00
per linear foot	
Creosoted timber trestles	- \$100.00
per linear foot	

ENGINEERING AND DESIGN DATA

Area 1 - Yemassee-Sheldon-Lobeco

Sheet 1 of 5

CANAL	No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (9)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
					TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
M-1A		4700	224	19	13	3	5	6956	3.5	38	--	--	3,136.80
Total - 1		4700						6956	3.5				
M-2A		3900	192	16	13	3	5	5772	2.9	38	--	30' - 24"	
L-1A		2500	56	6	13	3	5	3700	1.8	38	--	--	
M-2B		4600	400	30	13	3	5	6808	3.4	38	--	40' - 42"	8,205.00
Total - 2		11,000						16,280	8.1				
M-3A		2700	336	26	13	3	5	3996	--	38	40' - 36"	40' - 36"	
M-3B		7500	876	59	16	6	5	15,300	--	38	--	--	
L-1A		7200	448	33	13	3	5	10,656	5.3	38	--	--	
M-3C		5300	1524	93	19	9	5	13,727	6.0	55	--	15' R.C. Br.	
L-2A		5500	344	27	13	3	5	8140	4.0	38	--	20' - 24"	
M-3D		1400	1904	112	22	12	5	4410	1.8	62	--	40' - 24"	30,565.50
Total - 3		29,600						56,229	17.1				
M-4A		4800	228	19	13	3	5	7104	3.5	38	--	--	3,181.20
Total - 4		4800						7104	3.5				
M-5A		4600	516	38	13	3	5	6808	--	38	--	15' U.T. Br.	
M-5B		5800	1364	85	18	8	5	13,978	--	52	--	20' - 24"	
L-1A		6100	340	26	13	3	5	9028	4.5	38	--	20' - 42"	
M-5C		8900	2680	149	26	16	5	34,621	--	73	--	30' - C.T. Br.	
L-2A		1300	84	8	13	3	5	1924	1.0	38	--	--	
L-3A		2100	112	11	13	3	5	3108	1.5	38	--	--	
L-2B		1600	244	20	13	3	5	2368	1.2	38	--	30' - 48"	
L-2C			820	Present canal as constructed is considered adequate							--	20' - 48"	
M-5D		2600	3600	191	30	20	5	12,038	--	84	--	15' - C.T. Br.	52,463.40
Total - 5		33,000						83,873	8.2				
M-6A			72	Present canal as constructed is considered adequate							--	--	
L-1A			76	Present canal as constructed is considered adequate							--	--	
M-6B			872	Present canal as constructed is considered adequate							--	--	
L-2A			172	Present canal as constructed is considered adequate							--	--	
M-6C			1660	Present canal as constructed is considered adequate							--	--	
Total - 6		--						--	--				--

ENGINEERING AND DESIGN DATA

Area 1 - Yemassee - Sheldon - Lobocco

Sheet 2 of 5

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
M-7A	5900	868	58	16	6	5	12,036	-	46	-	-	27,744.20
M-7B	2500	1600	97	19	9	5	6475	-	55	-	15' U.T. Br.	
M-7C	4800	2364	134	24	14	5	16,896	-	68	-	30' R.C. Br.	
Total M-7	13,200						35,407	-		-	30' R.C. Br.	
M-8A	5100	296	23	13	3	5	7548	3.7	38	-	-	6,778.00
M-8B	3400	236	19	13	3	5	5032	2.5	38	-	-	
M-8C	8500	940	Present	canal	as constructed	is	considered	adequate		-	40' - 60"	
Total M-8							12,580	6.2		-	-	
M-9A	3500	332	26	13	3	5	5180	2.6	38	-	-	29,690.80
M-9B	3300	340	26	13	3	5	5180	-	38	-	50' - 42"	
M-9C	3300	80	8	13	3	5	4884	2.4	38	-	-	
M-9D	900	16	2	13	3	5	1332	0.7	38	-	-	
M-9E	3900	308	24	13	3	5	5772	2.9	38	-	40' - 42"	
M-9F	3100	1160	74	17	7	5	6882		49	-	-	
M-9G	3300	216	18	13	3	5	4884	2.4	38	-	40' - 24"	
M-9H	4500	1672	100	20	10	5	12,510	-	57	-	15' U. T. Br.	
M-9I	1200	1872	110	22	12	5	3780	1.5	62	-	40' - 60"	
Total M-9	27,200						50,404	12.5		-	-	
M-10A	3700	308	24	13	3	5	5476	2.7	38	-	-	59,385.70
M-10B	2400	216	18	13	3	5	3552	1.8	38	-	-	
M-10C	1900	584	41	14	4	5	3173	1.5	38	-	40' - 42"	
M-10D	1800	264	21	13	3	5	2664		38	-	-	
M-10E	5900	1196	76	17	7	5	13,098	-	49	-	40' - 42"	
M-10F	6200	368	28	13	3	5	9176	4.6	38	-	15' U.T. Br.	
M-10G	3900	1816	107	20	10	5	10,842	-	57	-	40' - 36"	
M-10H	3200	2124	123	22	12	5	10,080	-	62	-	15' R.C. Br.	
M-10I	3100	256	21	13	3	5	4588	2.3	38	-	-	
M-10J	2000	224	19	13	3	5	2960		38	-	-	
M-10K	5100	988	64	16	6	5	10,404	-	46	-	15' R.C. Br.	
M-10L	2100	1056	68	16	6	5	4284	-	46	-	-	
M-10M	3500	3592	190	30	20	5	16,205	-	84	-	-	
Total M-10	44,800						96,502	12.9		-	-	
M-11A	7100	372	28	13	3	5	10,508	2.6	38	-	-	5,584.80
Total M-11	7100						10,508	2.6		-	-	

ENGINEERING AND DESIGN DATA

Area 1 - Yemassee - Sheldon-Lobeco

Sheet 3 of 5

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.-f.-s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & NEW BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP Ft. (5)	BOTTOM Ft. (6)	AVERAGE DEPTH Ft. (7)						
M-12A L-1A M-12B Total-12	3700	180	15	13	3	5	5476	2.7	38	- - -	- - -	5,079.00
	2600	348	27	13	3	5	3848	1.9	38	- - -	- - -	
	900	612	43	14	4	5	1503	-	41	- - -	- - -	
	7200						10,827	4.6				
M-13A M-13B Total-13	2700	148	13	13	3	5	3996	2.0	38	- - -	50' - 30"	3,423.60
	1700	212	18	13	3	5	2516	1.2	38	- - -	- - -	
	4400						6512	3.2				
M-14A L-1A M-14B M-14C Total-14	3100	104	20	13	3	5	4588	2.3	38	- - -	- - -	7,939.60
	2000	56	12	13	3	5	2960	1.5	38	- - -	- - -	
	2800	264	43	13	3	5	4144	2.1	38	- - -	50' - 36"	
	2400	352	54	15	5	5	4440	2.1	44	- - -	- - -	
Total-14	10,300						16,132	8.0				3,535.60
M-15A L-1A M-15B Total-15	1900	60	6	13	3	5	2812	1.4	38	- - -	- - -	23,409.20
	1500	152	13	13	3	5	2220	1.1	38	- - -	- - -	
	1500	280	22	13	3	5	2220	1.1	38	- - -	20' - 36"	
	4900						7252	3.6				
M-16A L-1A M-16B L-2A L-3A M-16C M-16C L-4A M-16D M-16D L-5A Total-16	4900	92	9	13	3	5	7252	3.6	38	- - -	40' - 24"	3,423.60
	1100	48	5	13	3	5	1628	0.8	38	- - -	- - -	
	1700	240	20	13	3	5	2516	1.2	38	- - -	30' - 30"	
	2400	56	6	13	3	5	3552	1.8	38	- - -	- - -	
M-17A L-1A M-17B L-2A L-3A M-17C M-17C L-4A M-17D M-17D L-5A Total-17	2500	140	13	13	3	5	3700	-	38	- - -	- - -	6,852.00
	1500	496	36	13	3	5	2220	-	38	- - -	40' - 54"	
	4500	344	27	13	3	5	6660	-	38	- - -	30' - 36"	
	2200	900	16	16	6	5	4488	-	46	- - -	- - -	
M-18A L-1A M-18B M-18C Total-18	3500	140	13	13	3	5	5180	2.6	38	- - -	30' - 30"	23,409.20
	1400	1080	70	17	7	5	3108	-	49	- - -	- - -	
	25,700						40,304	10.0				
M-17A Total-17	4400	340	52	13	3	5	6512	3.2	38	- - -	50' - 30"	3,423.60
	4400						6512	3.2				
M-18A L-1A M-18B M-18C Total-18	2100	120	11	13	3	5	3108	1.5	38	- - -	40' - 30"	6,852.00
	2800	172	15	13	3	5	4144	-	38	- - -	- - -	
	2900	400	30	13	3	5	4292	-	38	- - -	- - -	
	7800	748	Present canal as constructed is considered adequate				11,544	1.5		- - -	- - -	

ENGINEERING AND DESIGN DATA

Area 1 - Yemassee-Sheldon-Lobacco

Sheet 4 of 5

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & NEW BRIDGES - & Size Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
N-19A	1700	80	8	13	3	5	2516	1.2	38	--	--	7,171.20
L-1A	1300	64	7	13	3	5	1924	1.0	38	--	--	
N-19B	1700	200	17	13	3	5	2516	1.2	38	--	--	
L-2A	2800	120	11	13	3	5	4144	2.1	38	--	--	
N-19C	1900	396	30	13	3	5	2812	--	38	--	30' - 42"	
Total-19	9400						13,912	5.5				
N-20A	3200	104	10	13	3	5	4736	2.4	38	--	--	7,682.40
L-1A	1400	144	13	13	3	5	2072	1.0	38	--	--	
N-20B	1400	280	22	13	3	5	2072	1.0	38	--	--	
L-2A	4500	240	20	13	3	5	6660	3.3	38	--	--	
N-20C	800	584	41	13	3	5	1184	--	38	--	--	
Total-20	11,300						16,724	7.7				
N-21A	4000	240	20	13	3	5	5920	2.9	38	--	30' - 42"	8,993.60
L-1A	3100	156	13	13	3	5	4588	2.3	38	--	30' - 24"	
L-2A	2500	96	9	13	3	5	3700	1.8	38	--	30' - 24"	
N-21B	1800	552	40	13	3	5	2664	1.3	38	--	15' U.T. Br.	
Total-21	11,400						16,872	8.3				
N-22A	2500	108	10	13	3	5	3700	1.8	38	--	30' - 18"	5,646.80
L-1A	2400	36	4	13	3	5	3552	1.8	38	--	--	
N-22B	1300	224	19	13	3	5	1924	1.0	38	--	40' - 36"	
Total-22	6200						9176	4.6			80' - 30"	
N-23A	1700	52	5	13	3	5	2516	1.2	38	--	--	1,114.80
Total-23	1700						2516	1.2				
N-24A	2100	56	6	13	3	5	3108	1.5	38	--	--	1,382.40
Total-24	2100						3108	1.5				
N-25A	2200	64	7	13	3	5	3256	1.6	38	--	40' - 24"	1,748.80
Total-25	2200						3256	1.6				
N-26A	2300	84	8	13	3	5	3404	1.7	38	--	--	5,086.00
L-1A	1400	48	5	13	3	5	2072	1.0	38	--	--	
N-26B	2800	200	17	13	3	5	4144	2.1	38	--	60' - 24"	
Total-26	6500						9620	4.8			40' - 24"	

WATER-CONTROL SYSTEM, 1967

ENGINEERING AND DESIGN DATA

Area 1 - Ycmasseac - Sheldon - Lobeco

Sheet 5 of 5

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c. f. s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
M-27A Total-27	2900 2900	56	6	13	3	5	4292 4292	2.1 2.1	38	-- --	-- --	1,917.60
M-28A L-1A M-28B Total-28	1200 1200 900 3300	44 24 78	5 3 8	13 13 13	3 3 3	5 5 5	1776 1776 1332 4884	0.9 0.9 0.7 2.5	38 38 38	-- -- -- -- -- -- -- --	30' - 18" -- -- -- --	2,353.20
M-29A L-1A M-29B Total-29	3300 1600 400 5300	128 64 200	23 13 33	13 13 13	3 3 3	5 5 5	4884 2368 592 7844	2.4 1.2 0.3 3.9	38 38 38	-- -- -- -- -- -- -- --	40' - 18" 30' - 30" 30' - 24" -- --	3,469.00
Area 1 Grand Total	310,900						567,130	152.4				326,963.80

ENGINEERING AND DESIGN DATA

Area 2 - Big Estate - Gardens Corner-Dalc

Sheet 1 of 2

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c. f. s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
M-1A	2900	300	24	13	3	5	4292	2.1	38	--	--	
L-1A	4800	228	19	13	3	5	7104	3.5	38	--	30' - 30"	
L-2A	5300	180	15	13	3	5	7844	3.9	38	--	30' - 30"	
L-1B	3000	548	40	13	3	5	4440	2.2	38	--	40' - 36"	
N-1B	3400	1016	66	16	6	5	6936	3.1	46	--	15' R.C. Br.	
L-3A	1900	60	6	13	3	5	2812	1.4	38	--	--	
N-1C	800	1140	72	16	6	5	1632	0.7	46	--	--	
L-4A	3300	80	8	13	3	5	4884	2.4	38	--	30' - 18"	
N-1D	7700	1788	106	19	9	5	19,943	8.7	55	--	30' - 30"	
L-5A	7200	744	101	14	4	5	12,024	5.8	41	--	--	
L-6A	3200	132	13	13	3	5	4736	2.4	38	--	--	
L-5B	1200	924	61	15	5	5	2220	1.0	44	--	--	
L-7A	3300	124	11	13	3	5	4884	2.4	38	--	30' - 30"	
L-5C	2800	1264	79	17	7	5	6216	2.8	49	--	40' - 48"	
L-8A	2400	228	19	13	3	5	3552	1.8	38	--	40' - 30"	
L-8B	5700	496	36	13	3	5	8436	4.2	38	--	50' - 54"	
L-5D	1900	1892	112	20	10	5	5282	2.2	57	--	30' R.C. Br.	
N-1E	1400	3724	196	28	18	5	5964	2.3	78	--	--	
N-1F	2800	3856	202	30	20	5	12,964	5.0	84	--	--	
L-9A	1400	40	4	13	3	5	2072	1.0	38	--	--	
N-1G	3800	4192	216	30	20	5	17,594	6.8	84	--	30' R.C. Br.	
N-1H	1500	4264	218	30	20	5	6945	2.7	84	--	--	
L-10A	5400	340	26	13	3	5	7992	4.0	38	--	--	
L-11A	3800	568	28	13	3	5	5624	2.8	38	--	40' - 18"	
L-10B	4700	1224	77	16	6	5	9588	4.3	46	--	15' C.T. Br.	
L-10C	2800	1448	89	18	8	5	6768	3.0	52	--	--	
N-1I	2300	5672	286	38	28	5	14,053	-	105	--	--	
N-1J	3300	6060	294	38	28	5	20,163	-	105	--	45' C.T. Br.	115,909.00
Total-1	94,000						216,944	82.5				
N-2A	5300	384	29	13	3	5	7844	3.9	38	--	40' - 48"	4,355.20
Total-2	5300						7844	3.9				
N-3A	4300	464	34	13	3	5	6364	3.2	38	--	--	
N-3B	3200	692	48	14	4	5	5344	2.6	41	--	15' R.C. Br.	
N-3C	1900	732	50	14	4	5	3173	1.5	41	--	--	
Total-3	9400						14,881	7.3				8,154.30
N-4A	6200	432	33	13	3	5	9176	4.6	38	--	--	

ENGINEERING AND DESIGN DATA

Area 2 - Big Estate - Gardens Corner - Dale

Sheet 2 of 2

CANAL	LENGTH	WATERSHED	DISCHARGE	CHANNEL DIMENSIONS			EXCAVATION	RT. OF WAY CLEARING	REQUIRED RT. OF WAY WIDTH	CULVERTS LOWERING	CULVERTS & BRIDGES - NEW	TOTAL ESTIMATED COST
No. (1)	Ft. (2)	Ac. (3)	c.f.s. (4)	TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)	Cu. Yds. (8)	Ac. (9)	Ft. (10)	Length & Size (11)	Length & Size (12)	Dollars (13)
M-4B	3500	544	39	13	3	5	5180	2.6	38	-- --	15' R.C. Br. 15' R.C. Br.	
M-4C	1800	576	41	13	3	5	2664	--	38	-- --	-- --	11,065.20
Total-4	11,500						17,020	7.2				
M-5A	3900	240	Present	canal	as constructed	is	considered	adequate	38	-- --	-- --	
I-1A	3900	192	16	13	3	5	5772	2.9		-- --	-- --	
M-5B	3900	604	Present	canal	as constructed	is	considered	adequate		-- --	15' R.C. Br.	4,101.60
Total-5	3900						5772	2.9				
M-6A	6700	392	30	13	3	5	9916	4.9	38	-- --	40' - 48" 40' - 42" 60' - 42"	
I-1A	6200	696	49	14	4	5	10,354	5.0	41	-- --	-- --	
M-6B	3400	1204	76	16	6	5	6936	3.1	46	-- --	15' C.T. Trees	
M-6C	3000	1344	83	17	7	5	6660	--	49	-- --	15' R.C. Br.	21,569.80
Total-6	19,300						23,950	8.1				
M-7A	2000	400	61	15	5	5	3700	1.7	44	-- --	30' - 54" 50' - 54" 30' - 48"	
M-7B	3700	656	93	18	8	5	8917	3.9	52	-- --	-- --	8,593.10
Total-7	5700						12,617	5.6				
M-8A	4700	184	32	13	3	5	6956	3.5	38	-- --	-- --	3,136.80
Total-8	4700						6956	3.5				
M-9A	1700	28	5	13	3	5	2516	1.2	38	-- --	-- --	
I-1A	1500	44	9	13	3	5	2220	1.1	38	-- --	-- --	
M-9B	700	82	16	13	3	5	1036	0.5	38	-- --	40' - 30"	
I-2A	3000	124	22	13	3	5	4440	2.2	38	-- --	40' - 15"	
M-9C	2000	290	46	14	4	5	3340	1.6	41	-- --	-- --	6,597.60
Total-9	8900						13,552	6.6				
M-10A	6300	284	22	13	3	5	9324	4.6	38	-- --	40' - 48"	
M-10B	2400	348	27	13	3	5	3552	--	38	-- --	-- --	7,140.40
Total-10	8700						12,876	4.6				
Area 2												
Grand Total	171,400						332,412	132.2				190,623.00

ENGINEERING AND DESIGN DATA

Area 3 - Port Royal Island

Sheet 1 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
M-1A	4700	180	31	13	3	5	6956	-	38	- - -	30' - 18" 30' - 24"	
Total-1	4700						6956	-				4,530.60
M-2A	2700	72	14	13	3	5	3996	-	38	- - -	40' - 24" 40' - 24"	
Total-2	2700						3996	-				2,981.00
M-3A	2800	140	25	13	3	5	4144	2.1	38	- - -	30' - 24" 30' - 30" 30' - 30" 30' - 36" 30' - 18" 30' - 36"	
L-1A	1700	36	13	13	3	5	2516	1.2	38	- - -		
M-3B	2900	224	37	13	3	5	4292	2.1	38	- - -		
Total-3	7400						10,952	5.4				6,714.60
M-4A	2900	172	30	13	3	5	4292	2.1	38	- - -	30' - 24" 30' - 36"	
Total-4	2900						4292	2.1				2,556.60
M-5A	4300	160	28	13	3	5	6364	3.2	38	40' - 18"	40' - 36" - - - - - -	
L-1A	1700	40	13	13	3	5	2516	1.2	38	- - -		
M-5B	2800	240	40	13	3	5	4144	2.1	38	- - -		
Total-5	8800						13,024	6.5				6,509.20
M-6A	2500	120	11	13	3	5	3700	1.8	38	- - -	40' - 24" 40' - 30" 40' - 30"	
M-6B	2800	340	26	13	3	5	4144	2.1	38	- - -		
Total-6	5300						7844	3.9				4,631.20
M-7A	6900	376	29	13	3	5	10,212	5.1	38	- - -	30' - 30" 30' - 42" 40' - 54" 40' - 54" 40' - 48" 40' - 48"	
M-7B	3100	448	33	13	3	5	4588	2.3	38	- - -		
Total-7	10,000						14,800	7.4				11,014.00

DOUGLASSPORT MAPS, INC. 1992

ENGINEERING AND DESIGN DATA

Area 3 - Port Royal Island

Sheet 2 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
M-8A	4800	196	17	13	3	5	7104	3.5	38	--	40' - 18" 40' - 18" 40' - 36" 40' - 36"	4,669.20
Total-8	4800						7104	3.5				
M-9A	4400	360	27	13	3	5	6512	3.2	38	--	--	
M-9B	7000	688	48	15	5	5	12,950	6.1	44	--	--	
L-1A	6900	396	30	13	3	5	10,212	5.1	38	--	--	
L-2A	1200	64	7	13	3	5	1776	0.9	38	--	--	
L-1B	2000	524	38	13	3	5	2960	1.5	38	--	15' C.T. Br.	
M-9C	2600	1352	84	18	8	5	6266	2.7	52	--	--	
M-9D	2200	1700	101	20	10	5	6116	2.6	57	--	30' R.C. Br.	
Total-9	26,300						46,792	22.1			30' R.C. Br.	27,417.60
M-10A		380	Present	16	6	5	considered adequate	5.6	46	--	40' - 48" 50' - 24" 50' - 30" 50' - 36"	
M-10B	6100	772	105	16	6	5	12,444			--	--	
M-10C	6000	1188	152	20	10	5	16,680	7.0	57	--	--	14,924.20
Total-10	12,100						29,124	12.6				
M-11A	3000	108	20	13	3	5	4440	2.2	38	--	40' - 24" 40' - 30"	6,289.60
M-11B	5400	300	48	13	3	5	7992	4.0	38	--	--	
Total-11	8400						12,432	6.2				
M-12A	4000	208	35	13	3	5	5920	2.9	38	--	--	
L-1A	1400	72	14	13	3	5	2072	1.0	38	--	--	
M-12B	1100	540	78	15	5	5	2035	1.0	44	--	40' - 42" 40' - 48"	
M-12C	6600	1028	134	18	8	5	15,906	7.0	52	--	--	
M-12D	1600	1224	155	20	10	5	4468		57	--	--	15,522.70
Total-12	14,700						30,381	11.9				
M-13A	3800	300	48	14	4	5	6346	3.1	41	--	40' - 48"	
L-1A	1900	280	45	14	4	5	3173	1.5	41	--	--	
M-13B	3600	912	121	22	12	5	11,340	4.6	62	--	--	
L-2A	5600	248	41	13	3	5	8288	4.1	38	--	40' - 24"	
M-13C	5800	2056	238	36	26	5	33,292	12.4	99	--	30' R.C. Br.	30,565.70
Total-13	20,700						62,439	25.7				

ENGINEERING AND DESIGN DATA

Area 3 - Port Royal Island

Sheet 3 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
N-14A Total-14	4800 4800	128	23	13	3	5	7104 7104	3.5 3.5	38	-- --	40' - 18"	3,365.20
N-15A Total-15	4400 4400	188	32	13	3	5	6512 6512	3.2 3.2	38	---	---	2,913.60
N-16A N-16B Total-16	4800 2400 7200	332 496	52 73	15 17	5 7	5	8880 5328 14,208	4.2 2.4 6.6	44 49	---	40' - 24"	6,534.40
N-17A I-1A N-17B Total-17	3300 2100 3100 8500	236 64 428	39 13 64	13 13 16	3 3 6	5	4884 3108 6324 14,316	2.4 1.5 2.8 6.7	38 38 46	---	60' - 18" 30' - 30" ---	7,558.80
N-18A N-18B N-18C Total-18	3000 2300 2500 7800	188 496 556	32 72 80	13 14 15	3 4 5	5	4440 3841 4625 12,906	2.2 1.9 -	38 41 44	---	30' - 42"	6,993.30
N-19A I-1A N-19B I-2A N-19C Total-19	2800 3500 1000 1700 2400 11,400	70 132 262 112 434	14 32 55 28 85	13 13 15 18	3 3 5 8	5	4144 5180 1850 2516 5784 19,474	2.1 2.6 0.9 1.2 -	38 38 44 38 52	---	40' - 24" 40' - 24" 40' - 24" 40' - 24" 40' - 36" 30' - 18" 70' - 18" 40' - 48" 40' - 42"	13,993.40
N-20A I-1A N-20B N-20C N-20D Total-20	3900 2300 1200 3500 2100 13,000	316 224 592 1084 1148	49 37 85 139 145	15 13 18 24 26	5 3 8 14 16	5	7215 3404 2892 13,320 8169 34,000	3.4 1.7 1.3 5.0 -	44 38 52 68 73	---	60' - 30" 40' - 30" 30' - 24" 30' - 48" 30' R.C. Br. 30' R.C. Br.	24,141.70

ENGINEERING AND DESIGN DATA

Area 3 - Port Royal Island

Sheet 4 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
M-21A	2300		28	13	3	5	3404	1.7	38	--	40' - 36"	4,124.40
L-1A	1200	28	(1200 ft. Storm drain necessary)								40' - 42"	
M-21B	250	148	(250 ft. Storm drain in place)				3404	1.7			40' - 36"	
Total-21	3750											
M-22A	600	44	12	13	3	5	888	0.4	38	--	40' - 30"	5,831.20
M-22B	2600	140	32	13	3	5	3848	1.9	38	--	40' - 36"	
M-22C	700	158	37	13	3	5	1036	0.5	38	--	--	
Total-22	3900						5772	2.8				
M-23A	1500	44	12	13	3	5	2220	1.1	38	--	40' - 18"	18,068.00
M-23B	3600	120	29	13	3	5	5328	2.6	38	--	40' - 30"	
L-1A	4600	180	41	13	3	5	6808	3.4	38	40' - 30"	40' - 26"	
M-23C	1600	384	77	16	6	5	3264	1.5	46	--	40' - 42"	
Total-23	11,300						17,620	8.6			60' - 42"	
M-24A	2300	256	55	15	5	5	4255	2.0	44	--	20' - 24"	7,947.40
M-24B	1600	320	66	16	6	5	3264	1.5	46	--	40' - 24"	
Total-24	3900						7519	3.5			60' - 48"	
M-25A		184	Present	canal as constructed is			considered adequate			--	40' - 36"	
M-25B		292	Present	canal as constructed is			considered adequate			--	--	560.00
Total-25	--											
Area 3												
Grand												
Total	208,750						392,971	162.8				240,357.60

ENGINEERING AND DESIGN DATA

Area 4 - Ladies Island - St. Helena Island

Sheet 1 of 10

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & NEW BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
M-1A L-1A L-2A M-1B Total-1	2000 900 1100 1700 5700	56 16 44 172	15 6 12 39	13 13 13 13	3 3 3 3	5 5 5 5	2960 1332 1628 2516 8436	1.5 0.7 0.8 1.2 4.2	38 38 38 38	-- -- -- -- --	-- 30' - 18" -- 30' - 36"	6,724.80
M-2A M-2B Total-2	2500 2400 4900	80 124	21 29	13 13	3 3	5 5	3700 3552 7252	1.8 1.8 3.6	38 38	-- --	50' - 24" 40' - 24" 30' - 30"	7,114.20
M-3A L-1A M-3B Total-3	1300 1200 500 3000	32 24 66	9 7 17	13 13 13	3 3 3	5 5 5	1924 1776 740 4440	1.0 0.9 0.4 2.3	38 38 38	-- -- --	30' - 18" 30' - 18" 40' - 24"	4,382.00
M-4A L-1A M-4B Total-4	1100 700 1900 3700	16 16 72	6 6 18	13 13 13	3 3 3	5 5 5	1628 1036 2812 5476	0.8 0.5 1.4 2.7	38 38 38	-- -- --	-- -- 30' - 24" 30' - 24" 30' - 30" 40' - 30"	5,787.60
M-5A Total-5	1200 1200	32	7	13	3	5	1776 1776	0.9 0.9	38	-- --	40' - 18"	986.80
M-6A L-1A M-6B Total-6	1200 700 2000 3900	40 12 80	8 3 16	13 13 13	3 3 3	5 5 5	1776 1036 2960 5772	0.9 0.5 1.5 2.9	38 38 38	-- -- --	-- -- 40' - 24"	2,893.60
M-7A M-7B L-1A M-7C Total-7	1100 5600 3900 700 11,300	124 420 104 548	22 63 19 79	13 16 13 18	3 6 3 8	5 5 5 5	1628 11,424 5772 1928 20,752	0.8 5.1 2.9 0.7 9.5	38 46 38 52	-- -- -- --	20' - 30" 30' - 36" 40' - 54" 40' - 30" --	11,047.60

ENGINEERING AND DESIGN DATA

Area 4 - Ladies Island - St. Helena Island

Sheet 2 of 10

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)	
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
N-8A L-1A N-8B Total-8	1600 1000 1100 3700	72 24 116	7 3 11	13 13 13	3 3 3	5 5 5	2368 1480 1628 5476	1.2 0.7 0.8 2.7	38 38 38	- - - - - - - - - - - -	- - - - - - - - - - - -	2,452.80	
N-9A Total-9	3100 3100	104	10	13	3	5	4588 4588	2.3 2.3	38	- - - - - -	- - - - - -	2,066.40	
N-10A Total-10	3000 3000	212	37	13	3	5	4440 4440	2.2 2.2	38	- - - - - -	- - - - - -	1,992.00	
N-11A L-1A L-2A L-1B L-3A N-11B N-11C L-4A L-10A Total-11	2600 1800 1700 2800 5500 1300 4100 1300 21,100	100 40 48 156 224 496 144 700	10 4 5 14 19 37 13 49	13 13 13 13 13 13 13 14	3 3 3 3 3 3 3 4	5 5 5 5 5 5 5 5	3868 2664 2516 4144 8140 1924 6068 2171 31,475	1.9 1.3 2.1 2.1 4.0 1.0 3.0 1.0 15.5	38 38 38 38 38 38 38 41	- 15' R.C. Br.	- -	- -	15,592.50
N-12A N-12B Total-12	2800 900 3700	168 184	14 16	13 13	3 3	5 5	4144 1332 5476	2.1 0.7 2.8	38 38	- - - - - - - - -	40' - 36" - - - - - -	3,042.80	
N-13A Total-13	2300 2300	80	8	13	3	5	3404 3404	1.7 1.7	38	- - - - - -	- - - - - -	1,531.20	
N-14A N-14B L-1A N-14C Total-14	1900 1800 2100 2800 8600	72 144 144 432	7 13 13 33	13 13 13 13	3 3 3 3	5 5 5 5	2812 2664 3108 4144 12,728	1.4 1.3 1.5 2.1 6.3	38 38 38 38	- - - - - - - - - - - - - - -	40' - 18" 30' - 24" - - - 40' - 30" 15' U.T. Br.	7,019.40	
N-15A L-1A L-2A N-15B	1200 1600 1300 2400	36 56 36 248	8 12 8 41	13 13 13 13	3 3 3 3	5 5 5 5	1776 2368 1924 3552	0.9 1.2 1.0 1.8	38 38 38 38	- - - - - - - - - - - -	- - - - - - - - - 40' - 42"		

ENGINEERING AND DESIGN DATA

Arca 4 - Ladies Island - St. Helena Island

Sheet 3 of 10

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c. f. s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & NEW BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
Total-15	6500						9620	13.0			40' - 36"	6,142.00
N-16A	2800	84	16	13	3	5	4144	2.1	38	--	30' - 18"	
L-1A	2800	80	16	13	3	5	4144	2.1	38	--	40' - 18"	
N-16B	1400	200	33	13	3	5	2072	1.0	38	--	----	5,174.00
Total-16	7000						10,360	5.2				
N-17A	2400	60	6	13	3	5	3552	1.8	38	--	40' - 24"	1,897.60
Total-17	2400						3552	1.8				
N-18A	1200	36	8	13	3	5	1776	0.9	38	--	----	
L-1A	900	20	4	13	3	5	1332	0.7	38	--	----	
N-18B	900	70	14	13	3	5	1332	0.7	38	--	----	
L-2A	1500	52	11	13	3	5	2220	1.1	38	--	----	
N-18C	600	128	23	13	3	5	888	0.4	38	--	----	
N-18D		152	Present canal as constructed is considered adequate									3,404.40
Total-18	5100						7548	3.8				
N-19A	2800	112	21	13	3	5	4144	2.1	38	--	----	
L-1A	1300	14	3	13	3	5	1924	1.0	38	--	----	
N-19B	1100	142	25	13	3	5	1628	0.8	38	--	----	3,478.80
Total-19	5200						7696	3.9				
N-20A	3700	140	13	13	3	5	5476	2.7	38	--	----	2,452.80
Total-20	3700						5476	2.7				
N-21A	3700	164	14	13	3	5	5476	2.7	38	--	----	2,452.80
Total-21	3700						5476	2.7				
N-22A	4900	236	19	13	3	5	7252	3.6	38	--	30' - 42"	
N-22B	900	284	22	13	3	5	1332	0.7	38	--	----	
Total-22	5800						8584	4.3				4,369.20
N-23A	2800	92	9	13	3	5	4144	2.1	38	--	30' - 30"	
N-23B	2300	168	14	13	3	5	3404	1.7	38	--	----	
L-1A	800	88	9	13	3	5	1184	0.6	38	--	30' - 30"	
L-1B	3200	184	16	13	3	5	4736	2.4	38	--	----	

ENGINEERING AND DESIGN DATA

Area 4 - Ladies Island - St. Helena Island

Sheet 4 of 10

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
M-23C Total-23	2900 12,000	488	71	14	4	5	4843 18,311	2.3 9.1	41	- - -	15' U.T. Br.	9,335.30
M-24A Total-24	2400 2400	52	11	13	3	5	3552 3552	1.8 1.8	38	30' - 15"	- - -	1,713.60
M-25A M-25B Total-25	900 2000 2900	36 76	8 15	13 13	3 3	5 5	1332 2960 4292	0.7 1.5 2.2	38 38	- - - - - -	40' - 18" - - -	2,131.60
M-26A L-1A M-26B Total-26	1000 900 700 2600	52 24 84	11 6 16	13 13 13	3 3 3	5 5 5	1480 1332 1036 3848	0.7 0.7 0.5 1.9	38 38 38	- - - - - - - - -	- - - 40' - 18" - - -	1,908.40
M-27A Total-27	1600 1600	40	8	13	3	5	2368 2368	1.2 1.2	38	- - -	30' - 18"	1,208.40
M-28A L-1A M-28B Total-28	600 1200 2700 4500	24 36 124	6 8 22	13 13 13	3 3 3	5 5 5	888 1776 3996 6660	0.4 0.9 2.0 3.3	38 38 38	- - - - - - - - -	- - - - - - - - -	2,988.00
M-29A L-1A M-29B L-2A Total-29	700 1000 700 1600 4900	14 22 44 24 80	3 4 9 6 16	13 13 13 13	3 3 3 3	5 5 5 5	1036 1480 1036 2368 7252	0.5 0.7 0.5 1.2 3.6	38 38 38 38 38	- - - - - - - - - 20' - 18" 50' - 18"	- - - - - - - - - - - - 40' - 18"	3,761.60
M-30A Total-30	1700 1700	38	4	13	3	5	2516 2516	1.2 1.2	38	- - -	30' - 18"	1,252.80
M-31A Total-31	2200 2200	50	5	13	3	5	3256 3256	1.6 1.6	38	- - -	30' - 18" 30' - 18" 30' - 18"	1,870.80

ENGINEERING AND DESIGN DATA

Arca 4 - Ladies Island - St. Helena Island

Sheet 5 of 10

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
N-32A	1800	36	4	13	3	5	2664	1.3	38	- - -	30' - 18"	1,557.20
Total-32	1800						2664	1.3			50' - 18"	
N-33A	1300	26	3	13	3	5	1924	1.0	38	- - -	30' - 18"	1,015.20
Total-33	1300						1924	1.0				
N-34A	1500	26	6	13	3	5	2220	-	38	- - -	- - -	1,332.00
Total-34	1500						2220	-				
N-35A	1600	24	6	13	3	5	2368	1.2	38	- - -	- - -	1,917.60
I-1A	1000	28	6	13	3	5	1480	0.7	38	- - -	- - -	
N-35B	300	54	11	13	3	5	444	0.2	38	- - -	- - -	
Total-35	2900						4292	2.1				
N-36A	1700	40	8	13	3	5	2516	1.2	38	- - -	- - -	1,114.80
Total-36	1700						2516	1.2				
N-37A	3600	80	16	13	3	5	5328	2.6	38	- - -	50' - 18"	2,608.40
Total-37	3600						5328	2.6				
N-38A	1600	52	11	13	3	5	2368	1.2	38	- - -	- - -	1,070.40
Total-38	1600						2368	1.2				
N-39A	1400	32	7	13	3	5	2072	1.0	38	- - -	- - -	3,716.40
I-1A	1300	24	6	13	3	5	1924	1.0	38	- - -	- - -	
I-2A	1400	16	4	13	3	5	2072	1.0	38	- - -	- - -	
I-1B	900	62	13	13	3	5	1332	0.7	38	- - -	- - -	
N-39B	600	106	20	13	3	5	888	0.4	38	- - -	- - -	
Total-39	5600						8288	4.1				
N-40A	2200	76	15	13	3	5	3256	1.6	38	- - -	- - -	1,456.80
Total-40	2200						3256	1.6				
N-41A	1600	36	8	13	3	5	2368	1.2	38	- - -	- - -	1,070.40
Total-41	1600						2368	1.2				

VERMONT STATE ENGINEER, 1967

ENGINEERING AND DESIGN DATA

Area 4 - Ladies Island - St. Helena Island

CANAL	LENGTH	WATERSHED	DISCHARGE	CHANNEL DIMENSIONS			EXCAVATION	RT. OF WAY CLEARING	REQUIRED RT. OF WAY WIDTH	CULVERTS LOWERING	CULVERTS & BRIDGES - NEW	TOTAL ESTIMATED COST
				TOP WIDTH	BOTTOM WIDTH	AVERAGE DEPTH						
No. (1)	Ft. (2)	Ac. (3)	c.f.s. (4)	Ft. (5)	Ft. (6)	Ft. (7)	Cu. Yds. (8)	Ac. (9)	Ft. (10)	Length & Size (11)	Length & Size (12)	Dollars (13)
N-42A Total-42	1200 1200	20	4	13	3	5	1776 1776	0.9 0.9	38	- - -	40' - 18"	986.80
N-43A L-1A N-43B Total-43	1200 800 1700 3700	20 28 84	2 3 8	13 13 13	3 3 3	5 5 5	1776 1184 2516 5476	0.9 0.6 1.2 2.7	38 38 38	- - - - - - - - -	- - - - - - - - -	2,452.80
N-44A Total-44	1500 1500	48	5	13	3	5	2220 2220	1.1 1.1	38	- - -	40' - 24"	1,288.00
N-45A L-1A N-45B L-2A N-45C Total-45	2500 4200 1500 5800 800 14,000	200 220 496 180 672	17 18 37 15 47	13 13 13 13 14	3 3 3 3 4	5 5 5 5 5	3700 4316 2220 8330 1336 21,822	1.8 3.1 1.1 3.7 0.6 10.3	38 38 38 38 41	- - - - - - - - - 40' - 30" - - -	- - - - - - - - - - - - - - -	9,840.60
N-46A N-46B Total-46	1300 3800 5100	48 160	5 14	13 13	3 3	5 5	1924 5624 7548	1.0 2.8 3.8	38 38	- - - - - -	40' - 36"	3,964.40
N-47A L-1A N-47B L-2A N-47C Total-47	4400 2200 2900 216 784 9500	224 84 392 216 784	19 8 30 Present canal as constructed is considered adequate Present canal as constructed is considered adequate	13 13 13	3 3 3	5 5 5	6512 3256 4292 14,060	3.2 1.6 2.1 6.9	38 38 38	40' - 24" - - - - - - - - - - - -	- - - - - - 40' - 54" - - - 40' - 36"	7,934.00
N-48A L-1A L-2A N-48B N-48C L-3A N-48D Total-48	1900 1600 2400 2800 280 168 9000	52 64 84 224 280 168 454	11 6 16 37 Present canal as constructed is considered adequate Present canal as constructed is considered adequate Present canal as constructed is considered adequate	13 13 13 13	3 3 3 3	5 5 5 5	2812 2368 3996 4144 13,320	1.4 1.2 2.0 2.1 6.7	38 38 38 38	- - - - - - - - - - - - - - - - - -	- - - - - - - - - 40' - 42" - - - - - -	6,678.00

ENGINEERING AND DESIGN DATA

Area 4 - Ladies Island - St. Helena Island

Sheet 7 of 10

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & NEW BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)					
M-49A M-49B M-49C Total-49	2200 3100 5300	148 308 392	26 49 Present	13 15 canal as constructed	3 5 canal as constructed	5 5 is considered adequate	1.6 2.7 adequate	38 44 4.3	-- -- --	40' - 36" 40' - 36" --	5,107.30
M-50A L-1A M-50B Total-50	5000 900 2600 8500	184 16 344	32 4 54	13 13 15	3 3 5	5 5 5	7400 1332 13,542	38 38 44	-- -- --	40' - 36" -- --	6,632.60
M-51A L-1A L-2A M-51B Total-51	1700 2100 1400 2400 7600	36 32 40 168	4 4 14	13 13 13	3 3 3	5 5 5	2516 3108 2072 3552 11,248	38 38 38 38 5.5	-- -- -- -- --	-- -- -- 40' - 30" --	5,432.40
M-52A M-52B M-52C Total-52	2100 1300 3400	112 132 148	21 24 Present	13 13 canal as constructed	3 3 canal as constructed	5 5 is considered adequate	3108 1924 5032	38 38 2.5	-- -- --	40' - 30" -- --	2,667.60
M-53A M-53B Total-53	2300 3700 6000	152 400	27 61	13 16	3 6	5 5	3404 7548 10,932	38 46 1.7	-- -- --	30' - 30" 40' - 30" --	6,774.00
M-54A M-54B L-1A M-54C L-2A L-2B M-54D Total-54	2000 4300 4200 4600 15,100	64 276 124 652 232 344 1108	13 44 Present Present 38 54 Present	13 14 canal as constructed canal as constructed 13 3 canal as constructed	3 4 canal as constructed canal as constructed 3 5 canal as constructed	5 5 is considered adequate is considered adequate 5 5 is considered adequate	2960 7181 adequate adequate 6216 6808 23,165	38 41 adequate adequate 38 38 11.5	-- -- -- -- -- -- --	30' - 24" 40' - 42" -- -- 40' - 42" 15' U.T. Br. --	11,790.50
M-55A L-1A L-2A M-55B Total-55	2500 1700 1000 600 5800	36 20 20 84	6 4 4 16	13 13 13 13	3 3 3 3	5 5 5 5	3700 2516 1480 888 8584	38 38 38 38 4.4	-- -- -- -- --	-- -- -- -- --	3,895.20

WATER-GEAR SYSTEM, 1957

ENGINEERING AND DESIGN DATA

Area 4 - Ladies Island - St. Helena Island

Sheet 8 of 10

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.-f.-s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & NEW BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
M-56A L-1A M-56B Total-56	1000 1600 2300 4900	28 20 132 24	6 4 24	13 13 13 13	3 3 3 3	5 5 5 5	1480 2368 3404 7252	0.7 1.2 1.7 3.6	38 38 38 38	- - - - - - - - - - - -	- - - - - - - - - - - -	3,255.60
M-57A L-1A M-57B L-2A M-57C L-3A M-57D L-4A M-57E L-5A L-6A Total-57	1200 1400 500 1700 500 4000 1100 2300 300 2700 2600 500 18,800	84 56 160 24 192 136 350 52 406 28 36 476	16 12 28 33 24 34 11 61 6 8 70	13 13 13 13 13 13 13 13 16 13 13 17	3 3 3 3 3 3 3 3 6 3 3 7	5 5 5 5 5 5 5 5 5 5 5 5	1776 2072 740 2516 740 5920 2035 3404 612 3996 1110 28,769	0.9 1.0 0.4 1.2 0.4 2.9 1.0 1.7 0.3 2.0 - 0.5 12.3	38 38 38 38 38 38 38 38 38 38 49	- -	- -	13,692.70
M-58A L-1A M-58B L-2A M-58C Total-58	3800 1600 800 1000 1500 8700	100 40 168 20 204	19 8 29 29 35	13 13 13 13 13	3 3 3 3 3	5 5 5 5 5	5624 2368 1184 1480 2220 12,876	2.8 1.2 0.6 0.7 1.1 6.4	38 38 38 38 38	- - - - - - - - - - - - - - - - - -	- - - - - - - - - - - - - - - - - -	5,782.80
M-59A L-1A M-59B Total-59	4200 3200 3700 11,100	228 196 508	38 33 74	13 13 14	3 3 4	5 5 5	6216 4736 6179 17,131	3.1 2.4 3.0 8.5	38 38 41	- - - - - - - - - - - -	- - - - - - - - - 15' C.T. Br.	8,439.30
M-60A Total-60	2500 2500	36	8	13	3	5	3700 3700	1.8 1.8	38	- - - - - -	- - - - - -	1,650.00
M-61A Total-61	2800 2800	38	8	13	3	5	4144 4144	2.1 2.1	38	- - - - - -	- - - 30' - 15"	1,981.20
M-62A L-1A M-62B	700 1500 1700	20 34 86	4 7 16	13 13 13	3 3 3	5 5 5	1036 2220 2516	0.5 1.1 1.2	38 38 38	- - - - - - - - -	- - - 40' - 15" 30' - 30"	

WATER RESOURCES

ENGINEERING AND DESIGN DATA

Area 4 - Ladies Island - St. Helena Island

Sheet 9 of 10

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
N-62C N-62D Total-62	3700 1100 8700	158 198	28 33	13 13	3 3	5 5	5476 1628 12,876	2.7 0.8 6.3	38 38	-- -- --	40' - 42" 40' - 36"	7,434.80
N-63A Total-63	1300 1300	36	8	13	3	5	1924 1924	1.0 1.0	38	-- -- --	-- -- --	877.20
N-64A Total-64	2400 2400	80	8	13	3	5	3552 3552	1.8 1.8	38	-- -- --	-- -- --	1,605.60
N-65A Total-65	2500 2500	92	9	13	3	5	3700 3700	1.8 1.8	38	-- -- --	40' - 24"	1,942.00
N-66A Total-66	2100 2100	48	11	13	3	5	3108 3108	1.5 1.5	38	-- -- --	-- -- --	1,382.40
N-67A N-67B N-67C Total-67	3300 2900 1100 2600 9900	112 188 36 300	21 32 8 48	13 13 13 15	3 3 3 5	5 5 5 5	4884 4292 1828 4810 15,614	2.4 2.1 0.8 2.3 7.6	38 38 38 44	-- -- -- 50' - 24" 30' - 36"	-- -- -- -- --	7,749.20
N-68A Total-68	1600 1600	48	11	13	3	5	2368 2368	1.2 1.2	38	-- -- --	-- -- --	1,070.40
N-69A L-1A L-1B N-69B Total-69	6700 4700 1700 1400 14,500	192 236 272 544	33 39 44 79	13 13 14 18	3 3 4 8	5 5 5 5	9916 6956 2839 3374 23,085	4.9 3.5 1.4 1.5 11.3	38 38 41 52	-- -- -- -- --	30' - 36" 40' - 24" 30' - 36" 50' - 42" 50' - 42"	13,127.50
N-70A L-1A N-70B Total-70	2000 1500 1700 5200	60 40 122	12 8 22	13 13 13	3 3 3	5 5 5	2960 2220 2516 7696	1.5 1.1 1.2 3.8	38 38 38	-- -- -- --	-- -- -- --	3,448.80

CHARTERED COPY WORKING 10/1/15

ENGINEERING AND DESIGN DATA

Area 4 - Ladies Island - St. Helena Island

Sheet 10 of 10

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
M-71A	700	6	1	13	3	5	1036	0.5	38	- -	- -	
L-1A	1400	20	4	13	3	5	2072	1.0	38	- -	- -	
M-71B	300	29	7	13	3	5	444	0.2	38	- -	- -	
L-2A	1600	14	3	13	3	5	2368	1.2	38	- -	- -	
M-71C	500	45	9	13	3	5	740	0.4	38	- -	- -	
Total-71	4500						6660	3.3				2,988.00
M-72A	1400	52	11	13	3	5	2072	1.0	38	- -	- -	
L-1A	2300	72	14	13	3	5	3404	1.7	38	- -	30' - 30"	
M-72B	1100	140	25	13	3	5	1628	0.8	38	- -	- -	
L-2A	2600	60	12	13	3	5	3848	1.9	38	- -	30' - 24"	
M-72C	1200	248	41	14	4	5	2004	1.0	41	- -	30' - 36"	
Total-72	8600						12,956	6.4				6,751.80
M-73A	3900	84	16	13	3	5	5772	2.9	38	- -	30' - 24"	
Total-73	3900						5772	2.9				2,820.60
M-74A	2200	32	7	13	3	5	3256	1.6	38	- -	30' - 18"	
Total-74	2200						3256	1.6				1,694.80
M-75A	1100	12	3	13	3	5	1628	0.8	38	- -	- -	
L-1A	1300	24	6	13	3	5	1924	1.0	38	- -	- -	
M-75B	1300	80	16	13	3	5	2220	1.1	38	- -	20' - 18"	
M-75C	2200	124	22	13	3	5	3256	1.6	38	- -	30' - 30"	
Total-75	6100						9028	4.5			20' - 36"	4,736.40
M-76A	1500	28	6	13	3	5	2220	1.1	38	- -	- -	
Total-76	1500						2220	1.1				996.00
Area-4 Grand Total	396,700						602,505	299.0				313,906.30

ENGINEERING AND DESIGN DATA

Area 5 - Camp St. Mary - Okatie - Pinckney Colony - Victoria Port

Sheet 1 of 5

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
M-1A L-1A M-1B Total-1	3800 4800 800 9400	100 152 268	2 3 5	13 13 13	3 3 3	5 5 5	5624 7104 1184 13,912	2.8 3.5 0.6 6.9	38 38 38	-- -- -- --	20' - 24" -- -- --	6,389.60
M-2A Total-2	2500 2500	108	2	13	3	5	3700 3700	1.8 1.8	38	-- --	30' - 30" --	1,956.00
M-3A Total-3	4500 4500	160	2	13	3	5	6660 6660	3.3 3.3	38	-- --	30' - 24" --	3,207.00
M-4A M-4B Total-4	1200 1500 2700	100 136	2 3	13 13	3 3	5 5	1776 2220 3996	0.9 1.1 2.0	38 38	-- -- --	30' - 30" 30' - 30" --	2,410.80
M-5A L-1A M-5B L-2A M-5C Total-5	1000 3900 900 3800 1200 10,800	36 176 232 120 376	1 3 4 2 6	13 13 13 13 13	3 3 3 3 3	5 5 5 5 5	1480 5772 1332 5624 1776 15,984	0.7 2.9 0.7 2.8 0.9 8.0	38 38 38 38 38	-- -- -- -- -- --	-- -- -- -- 30' - 54" --	7,900.20
M-6A Total-6	1900 1900	88	2	13	3	5	2812 2812	1.4 1.4	38	-- --	30' - 24" --	1,482.60
M-7A M-7B Total-7	1800 1900 3700	88 124	2 2	13 13	3 3	5 5	2664 2812 5476	1.3 1.4 2.7	38 38	-- -- --	30' - 24" 30' - 30" --	2,977.80
M-8A Total-8	2100 2100	72	2	13	3	5	3108 3108	1.5 1.5	38	40' - 24" --	-- --	1,674.40
M-9A M-9B Total-9	4100 3500 7600	312 456	5 8	13 13	3 3	5 5	6068 5180 11,248	3.0 2.6 5.6	38 38	-- -- --	40' - 36" -- --	5,614.40

ENGINEERING AND DESIGN DATA

Area 5 - Camp St. Mary - Okatie - Pinckney Colony - Victoria Port

Sheet 2 of 5

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & NEW BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
N-10A L-1A N-10B Total-10	5100 3900 4000 13,000	304 188 728	5 4 11	13 13 13	3 3 3	5 5 5	7548 5772 5920 19,240	3.7 2.9 2.9 9.5	38 38 38	- - - - - - - - - 40' - 42"	- - - - - - - - - - - -	9,294.00
N-11A Total-11	6700 6700	232	4	13	3	5	9916 9916	4.9 4.9	38	- - - - - -	- - - - - -	4,444.80
N-12A N-12B L-1A N-12C Total-12	3000 1800 2800 104 3200 10,800	160 248 104 656	14 20 10 46	13 13 13 13	3 3 3 3	5 5 5 5	4440 2664 4144 4736 15,984	2.2 1.3 2.1 2.4 8.0	38 38 38 38	- - - - - - - - - - - - 40' - 24" - - - 40' - 30" - - - - - -	- -	7,895.20
N-13A N-13B N-13C Total-13	3700 3200 2600 9500	512 824 912	37 55 60	13 14 15	3 4 5	5 5 5	5476 5344 4810 15,630	2.7 2.6 2.3 7.6	38 41 44	- - - - - - - - - - - -	- - - - - - - - - 15' R.C. Br. - - - - - - - - -	8,469.00
N-14A N-14B Total-14	2000 5000 7000	80 288	8 23	13 13 13	3 3 3	5 5 5	2960 7400 10,360	1.5 3.7 5.2	38 38	- - - - - - - - -	30' - 30" - - - - - -	4,974.00
N-15A L-1A L-1B N-15B N-15C Total-15	2500 3700 1300 4700 8000 20,200	296 200 260 992 1596	23 17 21 65 97	13 13 13 16 18	3 3 3 6 8	5 5 5 5 5	3700 5476 1924 9888 19,280 39,968	1.8 2.7 1.0 4.3 8.4 18.2	38 38 38 46 52	- - - - - - - - - - - - - - - - - -	- - - - - - - - - 40' - 42" 15' R.C. Br. - - - - - - - - -	19,622.40
N-16A N-16B Total-16	3700 5700 9400	420 756	32 52	13 14	3 4	5 5	5476 9519 14,995	2.7 4.6 7.3	38 41	- - - - - - - - -	40' - 54" - - - - - -	7,628.50
N-17A N-17B N-17C Total-17	2100 2900 1300 6300	224 348 540	19 27 39	13 13 13	3 3 3	5 5 5	3108 4292 1924 9324	1.5 2.1 2.1 4.6	38 38 38	- - - - - - - - - - - -	40' - 24" 40' - 42" - - - - - -	5,141.20

FORM EX-107 REV. 1957

ENGINEERING AND DESIGN DATA

Area 5 - Camp St. Mary - Okatie - Pinckney Colony - Victoria Port

Sheet 3 of 5

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS & LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
N-18A	2300	212	18	13	3	5	3404	1.7	38	--	40' - 24"	11,641.60
N-18B	4600	414	33	13	3	5	7104	3.5	38	--	--	
N-18C	2700	540	39	13	3	5	3996	2.0	38	--	--	
L-1A	1100	36	4	13	3	5	1628	0.8	38	--	--	
L-2A	2700	112	13	13	3	5	3996	2.0	38	--	--	
L-1B	2000	332	26	13	3	5	2960	1.5	38	--	--	
N-18D	1100	1064	69	16	6	5	2244	1.0	46	--	--	
Total-18	16,700						25,332	12.5		--	--	
N-19A	2900	260	21	13	3	5	4292	2.1	38	--	30' - 48"	42,373.40
N-19B	1500	336	27	13	3	5	2220	1.1	38	--	--	
L-1A	3800	368	28	13	3	5	5624	2.8	38	--	--	
N-19C	2000	760	48	14	4	5	3340	1.6	41	--	--	
L-2A	2400	196	17	13	3	5	3552	1.8	38	--	--	
N-19D	2100	1016	66	16	6	5	4284	1.9	46	--	15' U.T. Br.	
N-19E	1300	1144	73	17	7	5	2886	1.3	49	--	15' U.T. Br.	
N-19F	6800	1556	95	17	9	5	17,612	7.6	55	--	15' U.T. Br.	
L-3A	3500	140	13	13	3	5	5180	2.6	38	--	30' - 30"	
N-19G	5900	2068	120	17	7	5	13,098	5.8	49	--	30' - 18"	
L-4A	4500	196	17	13	3	5	6660	2.4	38	--	30' - 30"	37,455.00
L-5A	3300	136	12	13	3	5	4884	2.4	38	--	--	
L-4B	1300	396	30	13	3	5	1924	1.0	38	--	--	
N-19H	3800	2740	152	19	9	5	9842	4.3	55	--	--	
Total-19	45,100						85,398	39.6		--	--	
N-20A	3800	588	9	13	3	5	5624	2.8	38	--	15' U.T. Br.	
N-20B	1800	720	11	13	3	5	2664	1.3	38	--	30' - 30"	
L-1A	3700	244	4	13	3	5	5476	2.7	38	--	--	
N-20C	3500	1316	18	13	3	5	5180	2.6	38	--	20' - 24"	
L-2A	3500	200	4	13	3	5	5180	2.6	38	--	20' - 36"	
L-3A	4500	328	6	13	3	5	6660	3.3	38	--	20' - 54"	
L-2B	3000	744	11	13	3	5	4440	2.2	38	--	--	
N-20D	2000	2160	28	13	3	5	2960	1.5	38	--	--	
L-4A	8000	320	6	13	3	5	11,840	5.9	38	--	--	
N-20E	2200	2580	32	13	3	5	3256	1.6	38	--	--	
L-5A	6400	280	5	13	3	5	9472	4.7	38	--	15' U.T. Br.	
L-5B	3000	412	7	13	3	5	4440	2.2	38	--	30' - 54"	37,455.00
L-5C	3300	516	8	13	3	5	4884	2.4	38	--	--	
N-20F	3300	3200	39	13	3	5	76,960	26.2	38	--	--	
Total-20	52,000											

ENGINEERING AND DESIGN DATA

Area 5 - Camp St. Mary - Okatie - Pinckney Colony - Victoria Port

Sheet 4 of 5

CANAL	No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
					TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
N-21A L-1A M-21B L-2A L-2B M-21C Total-21		2000	132	3	13	3	5	2960	1.5	38	--	30' - 30"	12,640.20
		2200	236	4	13	3	5	3256	1.6	38	--	--	
		4500	536	9	13	3	5	6660	3.3	38	--	--	
		2900	264	5	13	3	5	4292	2.1	38	--	30' - 48"	
		3400	492	8	13	3	5	5032	2.5	38	--	30' - 24"	
M-22A N-22B Total-22		2300	1184	17	13	3	5	3404	12.7	38	--	--	2,592.40
		17,300						25,604	12.7		--	--	
		1200	60	6	13	3	5	1776	0.9	38	--	40' - 18"	
		2400	168	15	13	3	5	3552	1.8	38	--	--	
		3600						5328	2.7		--	--	
N-23A Total-23		2600	400	31	13	3	5	3848	1.9	38	--	40' - 24"	2,016.40
		2600						3848	1.9		--	--	
		3600	188	16	13	3	5	5328	2.6	38	--	30' - 24"	
		3600						5328	2.6		--	--	
											--	--	
N-25A L-1A N-25B Total-25		1300	1544	94	18	8	5	3133	1.4	52	--	--	7,828.50
		2100	140	13	13	3	5	3108	1.5	38	--	--	
		4300	1888	111	20	10	5	11,954	5.0	57	--	--	
		7700						18,195	7.9		--	--	
											--	--	
M-26A L-1A M-26B Total-26		3200	304	24	13	3	5	4736	2.4	38	--	30' - 24"	5,767.40
		3100	84	8	13	3	5	4588	2.3	38	--	30' - 30"	
		800	412	31	13	3	5	1184	0.6	38	--	15' U.T. Br.	
		7100						10,508	5.3		--	--	
											--	--	
M-27A L-1A L-2A L-1B M-27B Total-27		1200	412	31	13	3	5	1776	0.9	38	--	--	8,263.10
		6000	336	26	13	3	5	8880	4.4	38	--	--	
		1800	248	20	13	3	5	2664	1.3	38	--	--	
		1500	624	44	13	3	5	2220	1.1	38	--	--	
		1100	1068	69	14	4	5	1837	0.8	41	--	15' R.C. Br.	
M-28A N-28B Total-28		11,600						17,377	8.5		--	--	2,596.00
		1400	96	9	13	3	5	2072	1.0	38	--	40' - 24"	
		2100	208	18	13	3	5	3108	1.5	38	--	--	
		3500						5180	2.5		--	--	
											--	--	

ENGINEERING AND DESIGN DATA

Area 5 - Camp St. Mary - Okatie - Pinckney Colony - Victoria Port

Sheet 5 of 5

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
Area-5 Grand Total	298,900						481,371	220.9				236,853.30

ENGINEERING AND DESIGN DATA

Area 6 - Hilton Head Island

Sheet 1 of 3

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
M-1A M-1B Total-1	2100 700 2800	108 124 232	10 11 21	13 13 13	3 3 3	5 5 5	3108 1036 4144	1.5 0.5 2.0	38 38 38	-- -- --	40' - 24" -- --	2,135.20
M-2A M-2B M-2C Total-2	1600 2000 1000 4600	72 152 168 392	7 13 14 34	13 13 13 13	3 3 3 3	5 5 5 5	2368 2960 1480 6808	1.2 1.5 0.7 3.4	38 38 38 38	-- -- -- --	40' - 18" 40' - 36" -- --	3,806.40
M-3A M-3B Total-3	2100 1100 3200	132 152 284	12 13 25	13 13 13	3 3 3	5 5 5	3108 1628 4736	1.5 0.8 2.3	38 38 38	-- -- --	40' - 30" -- --	2,518.80
M-4A M-4B Total-4	2000 900 2900	80 112 192	8 10 18	13 13 13	3 3 3	5 5 5	2960 1332 4292	1.5 0.7 2.2	38 38 38	-- -- --	40' - 24" -- --	2,239.60
M-5A L-1A M-5B Total-5	1500 1200 1300 4000	80 36 144 260	8 3 13 24	13 13 13 13	3 3 3 3	5 5 5 5	2220 1776 1924 5920	1.1 0.9 1.0 3.0	38 38 38 38	-- -- -- --	-- -- 40' - 30" --	3,084.00
M-6A L-1A M-6B Total-6	3500 2700 1100 7300	176 88 280 544	15 8 22 45	13 13 13 13	3 3 3 3	5 5 5 5	5180 3996 1628 10,804	2.6 2.0 -- 4.6	38 38 38 38	-- -- -- --	-- -- 40' - 42" --	5,781.60
M-7A M-7B Total-7	4400 3700 8100	504 636 1140	36 45 81	13 13 13	3 3 3	5 5 5	6512 5476 11,988	3.2 2.7 5.9	38 38 38	-- -- --	15' R.C. Br. -- --	6,866.40
M-8A L-1A L-2A M-8B M-8C Total-8	8400 5800 4300 1700 3100 23,300	676 360 256 1384 1584 5600	47 27 21 86 96 277	14 13 13 17 18 13	4 3 3 7 8 3	5 5 5 5 5 5	14,028 8584 6364 3774 7471 40,221	6.7 4.3 3.2 1.7 3.3 19.2	41 38 38 49 52 52	-- -- -- -- -- --	-- -- 40' - 66" -- --	19,282.30

ENGINEERING AND DESIGN DATA

Arca 6 - Hilton Head Island

Sheet 2 of 3

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
M-9A Total-9	4600 4600	296	23	13	3	5	6808 6808	3.4 3.4	38	-- --	30' - 36"	3,482.40
M-10A L-1A M-10B Total-10	1600 2200 3300 7100	308 100 556	24 9 40	13 13 13	3 3 3	5 5 5	2368 3256 4736 10,360	1.2 1.6 2.4 5.2	38 38 38	-- -- -- -- -- -- -- --	-- -- -- -- 15' U.T. Br.	5,168.00
M-11A M-11B M-11C Total-11	5400 2000 1600 9000	272 364 404	22 28 30	13 13 13	3 3 3	5 5 5	7992 2960 2368 13,320	4.0 1.5 -- 5.5	38 38 38	-- -- -- -- -- -- -- --	40' - 24" 30' - 54" -- --	6,643.00
M-12A L-1A M-12B Total-12	3200 3700 1300 8200	148 132 412	13 12 31	13 13 13	3 3 3	5 5 5	4736 5476 1924 12,136	2.4 2.7 -- 5.1	38 38 38	-- -- -- -- -- -- -- --	-- -- -- -- 30' - 42"	6,252.00
M-13A L-1A L-1B L-1C M-13B Total-13	1800 2700 1500 1500 3500 11,000	44 164 224 272 480 632	4 14 19 22 35 Present	13 13 13 13 13	3 3 3 3 3	5 5 5 5 5	2664 3996 2220 2220 5180 Present canal as constructed is considered adequate	1.3 2.0 1.1 1.1 2.6 8.1	38 38 38 38 38	-- -- -- -- -- -- -- -- -- -- -- --	-- -- 40' - 36" 40' - 42" 40' - 42" 40' - 48" 30' - 48" 40' - 54"	11,614.00
M-14A M-14B L-1A L-1B M-14C Total-14	1700 1800 1500 1200 5200 11,400	88 144 144 192 580	8 13 13 16 41	13 13 13 13 13	3 3 3 3 3	5 5 5 5 5	2516 2664 2220 1776 7696 16,872	1.2 1.3 1.1 0.9 3.8 8.3	38 38 38 38 38	-- -- -- -- -- -- -- -- -- -- -- --	40' - 24" -- -- 30' - 36" -- -- 40' - 54"	9,203.60
M-15A Total-15	5800 5800	304	24	13	3	5	8584 8584	4.3 4.3	38	-- --	40' - 42"	4,537.20
M-16A M-16B	500 780	Present Present	Present Present	canal as constructed is canal as constructed is	canal as constructed is canal as constructed is	canal as constructed is canal as constructed is	canal as constructed is canal as constructed is	canal as constructed is canal as constructed is	canal as constructed is canal as constructed is	canal as constructed is canal as constructed is	canal as constructed is canal as constructed is	canal as constructed is canal as constructed is

ENGINEERING AND DESIGN DATA

Area 6 - Hilton Head Island

Sheet 3 of 3

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
M-16C Total-16	- - -	908	Present	canal	as constructed	is considered	- - -	- - -	- - -	- - -	50' - 48"	2,316.00
M-17A	3600	96	24	13	3	5	5328	2.6	38	- - -	30' - 18" 30' - 18" 30' - 18" 30' - 30" 30' - 30" 30' - 24" 30' - 24"	
M-17B M-17C L-1A M-17D Total-17	1800 1400 1400 1000 9200	152 168 64 248	35 38 17 52	13 13 13 15	3 3 3 5	5 5 5 5	2664 2072 2072 1850 8658	1.3 - - - 3.9	38 38 38 44	- - - - - - - - - - - - - - -	- - - - - - - - - - - - - - -	8,628.00
M-18A M-18B Total-18	2600 2500 5100	136 276	32 58	16 16	6 6	5 5	5304 5100 10,404	2.4 2.3 4.7	40 40	- - - - - -	- - - - - -	4,531.20
M-19A L-1A L-2A M-19B L-3A L-4A L-5A L-6A L-7A L-8A L-9A L-10A L-11A L-12A L-13A L-14A L-15A L-16A L-17A L-18A L-19A Total-19	2300 1200 2100 2000 2000 3400 3100 3200 2600 2100 3300 3000 6200 32,500	40 72 76 252 188 188 48 364 116 792 92 3000 148 1408	10 18 20 53 42 14 14 74 28 126 23 35 229	16 16 16 16 16 16 16 16 16 16 16 16 34	6 6 6 6 6 6 6 6 6 14 6 6 24	5 5 5 5 5 5 5 5 5 5 5 5 5	4692 2448 4284 4080 6936 2448 6882 5304 7392 6732 6120 33,294 90,612	2.1 1.1 1.9 1.8 3.1 1.1 3.1 2.4 3.0 3.0 2.8 12.5 37.9	40 40 40 40 40 40 40 43 62 62 40 40 88	- 40' - 48"	39,569.60	
M-20A M-20B Total-20	2000 3700 5700	88 368	8 28	13 13	3 3	5 5	2960 5476 8436	1.5 2.7 4.2	32 32	- - - - - -	40' - 24" - - -	4,082.80
Area-6 Grand Total	165,800						291,383	133.2				151,742.10

ENGINEERING AND DESIGN DATA

Area 7 - Prichardville - Bluffton - Daufuskie Island

Sheet 1 of 6

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
M-1A	3900	180	15	13	3	5	5772	2.9	38	--	30' - 18"	3,349.20
M-1B	900	192	16	13	3	5	1332	0.7	38	--	--	
Total-1	4800						7104	3.6		--	--	
M-2A	3800	136	12	13	3	5	5624	2.8	38	--	30' - 30"	12,211.80
L-1A	1300	148	13	13	3	5	1924	1.0	38	--	--	
L-2A	1900	64	7	13	3	5	2812	1.4	38	30' - 18"	--	
L-1B	1100	232	19	13	3	5	1828	0.8	38	--	--	
L-3A	3300	76	8	13	3	5	4884	2.4	38	--	30' - 15"	
L-1C	1200	336	26	13	3	5	1776	0.9	38	--	30' - 48"	
M-2B	4100	472	35	13	3	5	6068	3.0	38	--	--	
Total-2	16,700						24,716	12.3		--	--	
M-3A	3000	116	11	13	3	5	4440	2.2	38	--	30' - 30"	12,246.40
N-3B	3500	376	29	13	3	5	5180	2.6	38	--	--	
L-1A	2100	180	15	5	5	5	3108	1.5	38	--	--	
M-3C	3900	716	49	15	5	5	7215	3.4	44	--	15' U.T. Br. 15' U.T. Br.	
M-3D	2500	804	55	15	5	5	4625	2.2	44	--	--	5,751.60
Total-3	15,000						24,568	11.9		--	--	
M-4A	4000	236	19	13	3	5	5920	2.9	38	--	--	7,273.80
M-4B	3900	372	28	13	3	5	5772	2.9	38	--	30' - 42"	
Total-4	7900						11,692	5.8		--	--	
M-5A	2900	116	11	13	3	5	4292	2.1	38	--	30' - 24"	3,066.00
M-5B	4800	300	24	13	3	5	7104	3.5	38	--	30' - 30"	
M-5C	2500	412	31	13	3	5	3700	1.8	38	--	--	
Total-5	10,200						15,096	7.4		--	--	
M-6A	4000	344	27	13	3	5	5920	2.9	38	--	30' - 36"	3,066.00
Total-6	4000						5920	2.9		--	--	
M-7A	3200	148	13	13	3	5	4736	2.4	38	--	30' - 24"	
L-1A	1700	88	9	13	3	5	2516	1.2	38	--	--	
M-7B	2100	348	27	13	3	5	3108	1.5	38	--	--	
L-2A	4400	192	16	13	3	5	6512	3.2	38	--	30' - 36"	
M-7C	6100	836	58	13	3	5	11,285	5.3	44	--	--	7,273.80
L-3A	7300	288	23	13	3	5	10,804	5.4	38	--	30' - 48"	

ENGINEERING AND DESIGN DATA

Area 7 - Pritchardville - Bluffton - Daufuskie Island

Sheet 2 of 6

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
N-7D Total-7	1500 26,300	1175	75	16	6	5	3060 42,021	1.4 20.4	46	- - -	- - -	19,989.30
N-8A N-8B Total-8	4900 2500 7400	464 576	34 41	13 13	3 3	5 5	7252 3700 10,952	3.6 1.8 5.4	38 38	- - - - - - - - -	30' - 48" - - - - - -	5,529.60
N-9A N-9B N-9C Total-9	4700 5900 3400 14,000	328 608 712	25 43 49	13 13 14	3 3 4	5 5 5	6956 8732 5678 21,366	3.5 4.3 2.7 10.5	38 38 41	- - - - - - - - - - - -	20' - 54" 20' - 60" - - - - - -	10,601.80
N-10A N-10B Total-10	6100 3400 9500	292 456	23 34	13 13	3 3	5 5	9028 5032 14,060	4.5 2.5 7.0	38 38	- - - - - - - - -	20' - 36" - - - - - -	6,598.00
N-11A N-11B Total-11	2400 1000 3400	204 296	17 23	13 13	3 3	5 5	3552 1480 5032	1.8 0.7 2.5	38 38	- - - - - - - - -	30' - 42" - - - - - -	2,763.60
N-12A N-12B Total-12	3700 4400 8100	352 568	27 41	13 14	3 4	5 5	5476 7348 12,824	2.7 3.2 5.9	38 38	- - - - - - - - -	- - - - - - - - -	5,617.20
N-13A L-1A N-13B N-13C Total-13	4700 3400 6200 6600 20,900	144 92 520 840	13 9 38 56	13 13 13 15	3 3 3 5	5 5 5 5	6956 5032 9176 12,210 33,374	3.5 2.5 4.6 5.8 16.4	38 38 38 44	- - - - - - - - - - - - - - -	- - - - - - 30' - 36" 15' U.T. Br. - - -	15,852.20
N-14A L-1A N-14B Total-14	3400 2200 1900 7500	304 136 492	24 12 36	13 13 13	3 3 3	5 5 5	5032 3256 2812 11,100	2.5 1.6 1.4 5.5	38 38 38	- - - - - - - - - - - -	- - - - - - - - - - - -	4,980.00
N-15A N-15B Total-15	3200 4400 7600	304 476	24 35	13 13	3 3	5 5	4736 6512 11,248	2.4 3.2 5.6	38 38	- - - - - - - - -	20' - 42" - - - - - -	5,390.40

ENGINEERING AND DESIGN DATA

Area 7 - Pritchardville - Bluffton - Daufuskie Island

Sheet 3 of 6

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)		
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)								
N-16A L-1A N-16B N-16C Total-16	2700	160	14	13	3	5	3996	2.0	38	- - -	- - -	6,852.80		
	3400	200	18	13	3	5	5032	2.5	38	- - -	- - -			
	1700	460	34	3	5	5	2316	1.2	38	- - -	20' - 48"			
	1900	512	37	13	3	5	2812	1.4	38	- - -	- - -			
	9700						14,356	7.1						
N-17A N-17B N-17C Total-17	1500	224	19	13	3	5	2220	1.1	38	- - -	- - -	7,580.80		
	4900	488	36	13	3	5	7252	3.6	38	- - -	40' - 60"			
	3300	572	41	13	3	5	4884	2.4	38	- - -	- - -			
	9700						14,356	7.1						
N-18A N-18B Total-18	3500	564	40	13	3	5	5180	2.6	38	- - -	40' - 30"	7,155.60		
	4600	1128	72	17	7	5	10,212	4.5	49	- - -	- - -			
	8100						15,392	7.1						
N-19A L-1A N-19B N-19C L-2A L-3A L-3B L-3C N-19D L-4A L-5A L-4B L-4C N-19E Total-19	2500	164	15	13	3	5	3700	1.8	38	- - -	- - -	54,293.80		
	2100	168	15	13	3	5	3108	1.5	38	- - -	30' - 30"			
	6000	976	64	16	6	5	12,240	5.5	46	- - -	- - -			
	2000	1060	69	16	6	5	4080	1.8	46	- - -	- - -			
	4400	652	46	14	4	5	7348	3.5	41	- - -	- - -			
	1200	120	11	13	3	5	1776	0.9	38	- - -	40' - 36"			
	4100	688	48	14	4	5	6847	3.3	41	- - -	- - -			
	4500	968	63	16	6	5	9180	4.1	46	- - -	- - -			
	5300	3176	172	26	16	5	20,617	8.2	73	- - -	- - -			
	3900	440	33	13	3	5	5772	2.9	38	- - -	- - -			
	6500	684	48	14	4	5	10,855	5.2	41	- - -	30' - 48"			
	1612	98	18	8	5	5	14,701	6.4	52	- - -	40' - 60"			
	3000	1756	104	19	9	5	11,770	3.4	55	- - -	- - -			
	5200	5008	251	34	24	5	11,812	4.4	94	- - -	- - -			
	53,800						119,806	52.9						
	N-20A N-20B L-1A L-1B L-2A L-3A L-2B L-4A L-2C L-5A L-1C	4400	448	33	13	3	5	6512	3.2	38	- - -		- - -	
		3500	740	51	14	4	5	5845	2.8	41	- - -		- - -	
		4600	312	25	13	3	5	6808	3.4	38	- - -		20' - 48"	
		5200	580	41	13	3	5	7696	3.8	38	- - -		- - -	
3000		104	10	13	3	5	4440	2.2	38	- - -	- - -			
2900		196	17	13	3	5	4292	2.1	38	- - -	- - -			
1400		316	25	13	3	5	2072	1.0	38	- - -	- - -			
2700		68	7	13	3	5	3996	2.0	38	- - -	- - -			
900		396	30	13	3	5	1332	0.7	38	- - -	- - -			
3000		88	9	13	3	5	4440	2.2	38	- - -	- - -			
2700		1116	71	16	6	5	5508	2.5	46	- - -	15' U.T. Br.			

ENGINEERING AND DESIGN DATA

Area 7 - Pritchardville - Bluffton - Dautuskie Island

Sheet 4 of 6

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
N-20C N-20D Total-20	1200 2300 37,800	1988 2088	116 121	20 22	10 12	5 5	3336 7245 63,522	1.4 3.0 30.3	57 62	---	30' U.T. Br. ---	30,062.60
N-21A N-21B Total-21	2200 4400 6600	188 468	32 69	13 14	3 4	5 5	3256 7348 10,604	1.6 3.5 5.1	38 41	---	40' - 30" ---	5,119.20
N-22A Total-22	4200 4200	100	25	13	3	5	6216 6216	3.1 3.1	38	---	---	2,794.80
N-23A N-23B Total-23	3000 2900 2000 7900	124 152 324	29 36 67	13 13 16	3 3 6	5 5 5	4440 4292 4080 12,812	2.2 2.1 1.8 6.1	38 38 46	40' - 36" ---	40' - 36" 100' - 36"	7,913.60
N-24A N-24B Total-24	5700 2900 8600	340 460	26 34	13 13	3 3	5 5	8436 4292 12,728	4.2 2.1 6.3	38 38	---	20' - 48" 40' - 54" 40' - 54"	8,004.40
N-25A N-25B Total-25	2000 2200 3100 7300	148 132 431	13 12 32	13 13 13	3 3 3	5 5 5	2960 3256 4588 10,804	1.5 1.6 2.3 5.4	38 38 38	---	40' - 36"	5,421.20
N-26A N-26B Total-26	2700 2200 2300 7200	120 124 300	11 11 24	13 13 13	3 3 3	5 5 5	3996 3256 3404 10,656	2.0 1.6 1.7 5.3	38 38 38	---	---	4,786.80
N-27A Total-27	3900 3900	164	14	13	3	5	5772 5772	2.9 2.9	38	---	20' - 36"	2,881.60
N-28A N-28B N-28C Total-28	4700 2700 1600 1100 10,100	156 236 60 316	13 19 6 25	13 13 13 13	3 3 3 3	5 5 5 5	6956 3996 2368 1628 14,948	3.5 2.0 1.2 0.8 7.5	38 38 38 38	---	20' - 42" 20' - 42" ---	7,406.40

ENGINEERING AND DESIGN DATA

Area 7 - Pritchardville - Bluffton - Daufuskie Island

Sheet 5 of 6

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & NEW BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST - Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
M-29A	4400	192	16	13	3	5	6512	3.2	38	--	20' - 30"	5,445.60
M-29B	3000	304	24	13	3	5	4440	2.2	38	--	20' - 42"	
Total-29	7400						10,952	5.4		--	--	
M-30A	1900	120	11	13	3	5	2812	1.4	38	--	20' - 30"	10,084.70
M-30B	4000	312	25	13	3	5	5920	2.9	38	--	--	
L-1A	2100	48	5	13	3	5	3108	1.5	38	--	20' - 24"	
L-1B	4100	188	16	13	3	5	6068	3.0	38	--	--	
M-30C	2300	552	40	14	4	5	3841	1.9	41	--	--	
Total-30	14,400						21,749	10.7		--	--	
M-31A	2700	108	10	13	3	5	3996	2.0	38	--	--	1,798.80
Total-31	2700						3996	2.0		--	--	
M-32A	3000	132	12	13	3	5	4440	2.2	38	--	--	1,992.00
Total-32	3000						4440	2.2		--	--	
M-33A	4000	88	9	13	3	5	5920	2.9	38	--	--	2,646.00
Total-33	4000						5920	2.9		--	--	
M-34A	3400	52	5	13	3	5	5032	2.5	38	--	--	2,259.60
Total-34	3400						5032	2.5		--	--	
M-35A	3200	92	9	13	3	5	4736	2.4	38	--	--	2,140.80
Total-35	3200						4736	2.4		--	--	
M-36A	4000	80	8	13	3	5	5920	2.9	38	--	20' - 30"	6,238.40
M-36B	900	96	9	13	3	5	1332	0.7	38	--	--	
L-1A	1200	28	3	13	3	5	1776	0.9	38	20' - 18"	--	
M-36C	2500	168	14	13	3	5	3700	1.8	38	--	20' - 36"	
Total-36	8600						12,728	6.3		--	--	
M-37A	4600	248	20	13	3	5	6808	3.4	38	--	20' - 48"	6,851.60
M-37B	4300	432	33	13	3	5	6364	3.2	38	--	30' - 42"	
Total-37	8900						13,172	6.6				

ENGINEERING AND DESIGN DATA

Area 7 - Prichardville - Bluffton - Daufuskie Island

Sheet 6 of 6

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS LOWERING Length & Size (11)	CULVERTS & BRIDGES - NEW Length & Size (12)	TOTAL ESTIMATED COST Dollars (13)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)						
M-38A	4000	188	16	13	3	5	5920	2.9	38	--	20' - 42"	8,832.80
M-38B	3600	292	23	13	3	5	5328	2.6	38	--	20' - 48"	
M-38C	4100	420	32	13	3	5	6068	3.0	38	--	20' - 42"	
Total-38	11,700						17,316	8.5				
M-39A	5800	216	18	13	3	5	8584	4.3	38	--	20' - 30"	8,677.20
M-39B	2200	292	23	13	3	5	3256	1.6	38	--	--	
L-1A	2700	48	5	13	3	5	3996	2.0	38	--	--	
M-39C	1100	364	28	13	3	5	1628	0.8	38	--	30' - 48"	
Total-39	11,800						17,464	8.7				
M-40A	1800	92	9	13	3	5	2664	1.3	38	--	--	1,189.20
Total-40	1800						2664	1.3				
M-41A	4200	124	11	13	3	5	6216	3.1	38	--	--	2,794.80
Total-41	4200						6216	3.1				
M-42A	2500	84	8	13	3	5	3700	1.8	38	--	--	1,650.00
Total-42	2500						3700	1.8				
M-43A	4500	168	14	13	3	5	6660	3.3	38	--	--	2,988.00
Total-43	4500						6660	3.3				
M-44A	6000	120	11	13	3	5	8880	4.4	38	--	20' - 30"	4,188.00
Total-44	6000						8880	4.4				
M-45A	4100	120	11	13	3	5	6068	3.0	38	--	20' - 18"	2,812.40
Total-45	4100						6068	3.0				
Area-7 Grand Total	440,400						714,738	344.4				344,084.40















Figure No. 3

FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS
BEAUFORT COUNTY, SOUTH CAROLINA




INDEX TO MAP SHEETS

CONVENTIONAL SIGNS

	Primary Road System
	Federal Highway
	State Highway
	County Road
	School
	Church
	County Line
	Planning Unit Boundary and Number
	Watershed Boundary
	Main
	Lateral
	Indicates existing canals or natural drainage in swamp


FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS IN BEAUFORT COUNTY, SOUTH CAROLINA

1



(Joins inset, sheet 2)

(Joins sheet 3)




This is one set of maps prepared by the Soil Conservation Service, U.S. Department of Agriculture, for a feasibility study of requirements for main ditch drainage canals in Beaufort County, South Carolina. The maps have been prepared in cooperation with Beaufort County Soil and Water Conservation District and under the financial sponsorship of Beaufort County. For information regarding the complete feasibility study report, write the Soil Conservation Service, U.S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photographs flown in 1965. Maps were prepared and surveys executed in 1969.


FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS IN BEAUFORT COUNTY, SOUTH CAROLINA

2

(Joins inset, sheet 2)



(Joins Inset, sheet 2)



(Joins sheet 7)



(Joins sheet 3)

FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS IN BEAUFORT COUNTY, SOUTH CAROLINA

(Joins sheet 1)

3



(Joins sheet 5)

(Joins sheet 4)

(Joins sheet 2)

This is one set of maps prepared by the Soil Conservation Service, U.S. Department of Agriculture, for a feasibility study of requirements for main ditch drainage canals in Beaufort County, South Carolina. The maps have been prepared in cooperation with Beaufort County Soil and Water Conservation District and under the financial sponsorship of Beaufort County. For information regarding the complete feasibility study report, write the Soil Conservation Service, U.S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photographs flown in 1965. Maps were prepared and surveys executed in 1969.

0 1/2 1 Mile Scale 1:50,000 (Approximate) 0 5000 Feet

④

Combahee River

Wimbee

Creek

Bull

River

INTRA

COASTAL

Coosaw


WATERWAY

River

(802)

M-33


(Joins sheet 6)



FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS IN BEAUFORT COUNTY, SOUTH CAROLINA

(Joins sheet 3)

5



(Joins sheet 6)

This is one set of maps prepared by the Soil Conservation Service, U.S. Department of Agriculture, for a feasibility study of requirements for main ditch drainage canals in Beaufort County, South Carolina. The maps have been prepared in cooperation with Beaufort County Soil and Water Conservation District and under the financial sponsorship of Beaufort County. For information regarding the complete feasibility study report, write the Soil Conservation Service, U.S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photographs flown in 1965. Maps were prepared and surveys executed in 1969.

(Joins Inset, sheet 2)



(Joins sheet 8)

0 1/2 1 Mile Scale 1:50 000 (Approximate) 0 5000 Feet

FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS IN BEAUFORT COUNTY, SOUTH CAROLINA
(Joins sheet 4)

6




(Joins sheet 9)

This is one set of maps prepared by the Soil Conservation Service, U.S. Department of Agriculture, for a feasibility study of requirements for main ditch drainage canals in Beaufort County, South Carolina. The maps have been prepared in cooperation with Beaufort County Soil and Water Conservation District and under the financial sponsorship of Beaufort County. For information regarding the complete feasibility study report, write the Soil Conservation Service, U.S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photographs flown in 1965. Maps were prepared and surveys executed in 1969.

FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS IN BEAUFORT COUNTY, SOUTH CAROLINA

(Joins inset, sheet 2)



(Joins sheet 10)

(Joins sheet 8)

FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS IN BEAUFORT COUNTY, SOUTH CAROLINA

(Joins sheet 5)

8




(Joins sheet 7)



(Joins sheet 11)

(Joins sheet 9)



FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS IN BEAUFORT COUNTY, SOUTH CAROLINA

(Joins sheet 6)

This is one set of maps prepared by the Soil Conservation Service, U.S. Department of Agriculture, for a feasibility study of requirements for main ditch drainage canals in Beaufort County, South Carolina. The maps have been prepared in cooperation with Beaufort County Soil and Water Conservation District and under the financial sponsorship of Beaufort County. For information regarding the complete feasibility study report, write the Soil Conservation Service, U.S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photographs flown in 1965. Maps were prepared and surveys executed in 1969.



(Joins sheet 8)



FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS IN BEAUFORT COUNTY, SOUTH CAROLINA

(Joins sheet 7)

(Joins sheet 11)



(Joins sheet 12)

FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS IN BEAUFORT COUNTY, SOUTH CAROLINA

(Joins sheet 8)

11

2

This is one set of maps prepared by the Soil Conservation Service, U.S. Department of Agriculture, for a feasibility study of requirements for main ditch drainage canals in Beaufort County, South Carolina. The maps have been prepared in cooperation with Beaufort County Soil and Water Conservation District and under the financial sponsorship of Beaufort County. For information regarding the complete feasibility study report, write the Soil Conservation Service, U.S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photographs flown in 1965. Maps were prepared and surveys executed in 1969.



(Joins sheet 10)

(Joins inset, sheet 12)

0 1/2 1 Mile Scale 1:50 000 (Approximate) 0 5000 Feet

